




# PRECON

FOR CONCRETE AND BLOCK





# PRECON

FOR CONCRETE AND BLOCK



تم بعون الله تعالى افتتاح قسم الطابوق و الخرسانة بمصنع الإنشاءات المسبقة الصنع (بريكون للخرسانة والطابوق) بتاريخ 1/1/2011م بطاقة إنتاجية 25000 طابوقة كل 8 ساعات على مساحة إجمالية 25000 م<sup>2</sup> حيث تمتلك الشركة حوالي 25 خلاطة مع 5 مضخات و عدد 2 مصانع خلطة و تبلغ الطاقه الإنتاجية لكل مصنع 120 م<sup>3</sup> حيث اننا نوفر جميع أنواع الخرسانة عالية القوة و يمكننا توفير مجموعة متنوعة من أنواع الأسمنت المختلفة بما في ذلك OPC و SRC و Micro Silica كما يمكننا توريد الخرسانة لجميع قطاعات السوق في المنطقة الشرقية يمكننا توريد الخرسانة الجاهزة من 3 م<sup>3</sup> إلى 3000 م<sup>3</sup> . وقد تم اختيار جميع معدات المصنع من أحدث المعدات و الموديلات والتي تستخدم تقنيات التصنيع الحديثة و تم انتقاء أفضل المواد الخام من الأسمنت و الكنكري و الرمل و الماء الحلو حيث تم فحص عينات عشوائية من الإنتاج من جميع الأصناف في مختبرات معتمدة لدى ارامكو السعودية وشركة سابك و الهيئة الملكية وقد تم اجتياز جميع إختبارات الفحص بنتائج عالية و مطابقة للمواصفات العالمية القياسية حسب الكود الأمريكي ( ASTM ) ، ولقد حاز المصنع مؤخرًا على شهادة الأيزو ( ISO 9001 ) لتطبيق معايير الجودة العالمية .


**By the grace of Allah, the brick and concrete department was opened at the prefabricated construction factory (Brecon Concrete and Bricks) On 1/1/2011 with a production capacity of 25,000 bricks every 8 hours on a total area of 25,000 m<sup>2</sup> The company owns about 25 mixers with 5 pumps and 2 mixing plants and the production capacity of each plant is 120 m<sup>3</sup> As we provide all types of high-strength concrete and we can provide a variety of different types of cement including OPC, SRC and Micro Silica. We can also supply concrete to all market sectors, in the Eastern Province We can supply ready-mix concrete from 3 m<sup>3</sup> to 3000 m<sup>3</sup>. All the factory equipment was selected from the latest equipment and models that use modern manufacturing techniques. The best raw materials were selected from cement, aggregate, sand and fresh water. Random samples of production from all types were examined in laboratories accredited by Saudi Aramco, SABIC and the Royal Commission. All inspection tests were passed with high results and conformed to international standard specifications. According to the American code (ASTM), the factory has recently obtained the ISO (9001) certificate for applying international quality standards.**






**PRECON**  
FOR CONCRETE AND BLOCK





## GENERAL INFORMATION OF THE COMPANY

- ▶ Name ▶ ▶ ▶ PRECON FOR CONCRETE AND BLOCK
- ▶ Commercial Registration ▶ ▶ ▶ 2050041727
- ▶ Ministerial Decree ▶ ▶ ▶ Industrial License No: 1203
- ▶ Address ▶ ▶ ▶ Dammam, Abu Hadriyah Highway
- ▶ Mailing Address ▶ ▶ ▶ P.O Box # 2447, Dammam 31451, Kingdom of Saudi Arabia.
- ▶ Website Address ▶ ▶ ▶ [www.precon.sa](http://www.precon.sa)
- ▶ E-mail ▶ ▶ ▶ [precon@precon.sa](mailto:precon@precon.sa)
- ▶ Telephone No ▶ ▶ ▶ +96613-8377773
- ▶ Fax No ▶ ▶ ▶ +96613-8373218



## Industrial Licence



وزارة التجارة  
Ministry of Commerce

شهادة تسجيل فرع مؤسسه

الرقم: ٧٠١٣٤٩٨٩٧٢  
التاريخ: ٢٠٥٠٠٤١٧٢٧ هـ  
١٤٢٣/٠٩/١٩ هـ

اسم التاجر: على عبدالله محمد مرعي آل حصان  
رقم السجل المدني/بطاقة الأحوال: ١٠١٨٢٧٥٩٧٢  
المركز الرئيسي: الدمام  
ص.ب: \_\_\_\_\_  
الرمز البريدي: \_\_\_\_\_  
هاتف: \_\_\_\_\_

الاسم التجاري للفرع: مصنع الإثشاءات المسبقة الصنع للصناعة  
العنوان: الدمام / طريق ابوهريرة مخطط ٣ غرب الأوجام  
ص.ب: \_\_\_\_\_  
الرمز البريدي: \_\_\_\_\_  
هاتف: \_\_\_\_\_

النشاط: صناعة البنك الأسمنتي المفرغ والأجر صناعة قواطع ولواح واطر ومباني جاهزة من الخرسانة سابقة الصنع


رأس المال: ٥٠٠٠٠٠٠٠٠  
اسم المدير أو الوكيل المفوض: عبدالمجيد بن علي بن عبدالله آل حصان  
الجنسية: سعودي  
رقم السجل المدني - الإقامة: ١٠١٨٢٧٦٠١٢  
سلطات المدير

يشهد مكتب السجل التجاري بمدينة الدمام بأنه تم تسجيل هذه المؤسسة بسجل مدينة الدمام  
وتنتهي صلاحية الشهادة في ١٤٤٦/١٢/١٩ هـ بموجب الإيصال رقم: ٥٩٧٤٥٩١٩ و تاريخ: ١٤٤٦/١١/١٢ هـ

مدير السجل التجاري:  
التوقيع: \_\_\_\_\_  
تاريخ الميلاد: ١٤٠٤ هـ  
مصدره: الدمام

يُلف صالح الطاسان

To Verify the information of this certificate visit <http://v.mci.gov.sa>  
يمكنك التحقق من صحة هذه الشهادة بالدخول على <http://v.mci.gov.sa>





## Chamber Membership



### شهادة الاشتراك - Membership Certificate



The Unified Number: 7013498972

الرقم الموحد المنشأ: 7013498972

Classification : Fourth

الدرجة: الرابعة

Date of Issue : 27/02/2023

تاريخ الاصدار : 07/8/1444

Asharqia Chamber Certifies that:

تشهد الغرفة التجارية الصناعية بالمنطقة الشرقية بأن

PRECAST STRUCTURES FACTORY

مصنع الانشاءات المسبقة الصنع

Membership No : 84319

رقم الاشتراك: 84319

Registered with Chamber since : 06/05/2007 and

مشاركة في الغرفة منذ : 19/04/1428

the certificate expires on : 15/06/2025

وينتهي سريان هذه الشهادة في : 19/12/1446

,2447, الدمام, 31451

,31451, الدمام, 2447



SF-MEMBD-04 Rev. 10 Issued 01.MAR. 2021

<https://www.chamber.org.sa/Verify/Cert> يمكنك التحقق من صحة هذه الشهادة





## Industrial Licence



وزارة الصناعة والتجارة  
المملكة العربية السعودية

### ترخيص منشأة صناعية

#### استثمار وطني

رمز المنشأة ١٥١٢-٣  
نوع القرار تعديل  
تاريخ الترخيص ١٤٤١-٠٤-٠٨  
رقم القرار ١١  
تاريخ القرار ١٤٤١-٠٤-٠٨  
تاريخ الانتهاء ١٤٤٤-٠٤-٠٨

اسم المنشأة الصناعية مصنع الريشبات المسبقة الصنع  
السجل التجاري للمنشأة الصناعية ٢٠٥٠٠٤١٧٧  
مالك المنشأة علي بن عبدالله بن محمد آل حضان  
رقم الهوية ١٠١٨٧٥٩٧٢  
الجنسية العربية السعودية  
النشاط الرئيسي صنع اصناف من الخرسانة والسمنت والجص / ٢٣٩٥

عدد العمالة ٩٠  
حجم الاستثمار ١٥٠٣٦١٤٥٠٠٠  
تسعون فرداً  
خمسة عشر مليون و ستة و ثلاثون ألفاً و مائة و خمسة و أربعون ريال

الوحدة	الطاقة الإنتاجية	النشاط الصناعي	وصف المنتج	رمز المنتج
متر مربع	٩٠٠٠٠	صناعة قواطع وألواح ومباني جاهزة من الخرسانة سابقة الصنع	ألواح خرسانية مسبقة الصنع	٦٨١٠٩١٠٠
متر مربع	١٢٠٠٠٠	صناعة قواطع وألواح ومباني جاهزة من الخرسانة سابقة الصنع	حوائط داخلية مسبقة الصنع	٦٨١٠٩١٠٠
وحدة	٢٥٠٠٠٠٠	صناعة البلك الأسمنتي المفرغ والآخر	طابوق بناواعة	٦٨١٠١١٠٠



وزير الصناعة والتجارة المعدنية

بندر بن إبراهيم الخريف


الخريف

رؤية ٢٠٣٠  
VISION 2030  
المملكة العربية السعودية  
KINGDOM OF SAUDI ARABIA






## PRECON ORGNIZATIONAL CHART







## LIST OF PERSONNELS & EMP

S.No	Category	Nos
	General Manager	1
▶ 1	Operational Manager	1
▶ 2	Administration Deptt:	2
▶ 3	Technical Department	12
▶ 4	Financial Department:	5
▶ 5	Public Relations & Marketing	3
	<b>Total</b>	<b>23</b>

▶ 1	Specialist Forms Fabricators	5
▶ 2	Professional Welders	15
▶ 3	Steel Fixers	20
▶ 4	Carpenters	6
▶ 5	Masons	20
▶ 6	Sandblasters	5
▶ 7	Precast Erectors	30
▶ 8	Plumbers	3
▶ 9	Electricians	5
▶ 10	Drivers	5
▶ 11	Labor	25
▶ 12	Batching Plant Operators	3
▶ 13	Auto Electricians	2
▶ 14	Hydraulic & Diesel Mechanics	5
▶ 15	Stressing Foremen	3

**Total**

**152**




# Block products



## Solid Blocks

### S20(solid Block) Technical Date


Code	S20
Depth (cm)	S20
Blocks/Bundle	30




## Hourdi Blocks

### Hourdi 20 Technical Date

Code	S20
Depth (cm)	S20
Blocks/Bundle	30



## Insulation Blocks




### Technical and Physical Date of Insulation

Expnaded Polystyrene = 22-24kg/m  
Dimension Stability at 80%= 0.5%  
Thermal expansion coefficirnt =0.07mm/mc  
Water vapor transmission resistance =150

### Technical and Physical Date

Block per m<sup>2</sup> 12.5nos.  
Wall thickness 20cm  
Block height 20cm  
Block length 40cm

## Insulation Blocks



Heat flow density  $q = 10.6 \text{ w/m}^2$   
Heat storage  $Q = 54.5 \text{ kcal/m}^2 \text{ oc}$   
Cooling time  $h = Qx \ 1/u=124\text{hours}$   
U-value  $U=0.41$


### Technical and Physical Date

Block per m<sup>2</sup> 12.5nos.  
Wall thickness 30cm  
Block height 20cm  
Block length 40cm

## Hollow Block U

### Technical and Physical Date


Block per m<sup>2</sup> 12.5nos.  
Wall thickness 20cm  
Block height 20cm  
Block length 20cm



## Hollow Blocks


### 400x200x100mm Technical Date

Stone	Hollow Block
Thickness of stone -cm	10
Area / Stone -cm <sup>2</sup>	500
Stones per m <sup>2</sup>	12.5




### 400x200x150mm Technical Date

Stone	Hollow Block
Thickness of stone -cm	15
Area / Stone -cm <sup>2</sup>	800
Stones per m <sup>2</sup>	12.5




### 400x200x200mm Technical Date

Stone	Hollow Block
Thickness of stone -cm	20
Area / Stone -cm <sup>2</sup>	800
Stones per m <sup>2</sup>	12.5




### 400x200x250mm Technical Date

Stone	Hollow Block
Thickness of stone -cm	25
Area / Stone -cm <sup>2</sup>	800
Stones per m <sup>2</sup>	12.5



### 400x200x300mm Technical Date


Stone	Hollow Block
Thickness of stone -cm	30
Area / Stone -cm <sup>2</sup>	800
Stones per m <sup>2</sup>	12.5



# PRECON READY MIX & BLOCK Mix Design Report





 <b>بريكون</b> للخرسانة والطابوق	<b>PRECON READY MIX &amp; BLOCK</b> <b>Mix Design Report</b>		
Date:	01-01-2024	Mix Code:	1002
Client:	GENERAL		
Project:	GENERAL		

**Mix Properties:**

Strength:	3000 Psi (C20)	Min. Cement Content/m3:	270 kg	Cement Type:	I&V
W/C. Ratio	0.66	Max. Size of Agg.:	20 mm	Max. Slump:	150±40 mm

Ingredients	Sp. Gr. SSD	SSD Wt	% of Agg.	Volume/Lt	Source
Cement (Kg)	3.15	270		61.9	Saudi Cement
Micro Silica (Kg)	2.2				Al Rashed
Free Water (Lt)	1	180		180	Precon R/O Plant
Agg. 20mm (Kg)	2.578	560		267.6	Summan
Agg. 10mm (Kg)	2.573	510		151.6	Summan
Sand (Kg)	2.625	790		327.6	Local Dune
Admx-D-10 (L)	1.12	2.7		1.071428571	Fosam
Admx-G-62 (L)	1.13			0	
Admx-Lt.		0		0	
Air Content	%	2		20	
Total		2312		1000	

**Fresh Concrete Properties:**

Unit Wt Kg/M:	2312	Air Content:	2%	Slump:	140	Temp ©	28
Initial Setting Time (Min):		Final Setting Time(Mine):					

**Harden Concrete Properties:**

No.	Density (Kg/m)	Age (Days)	Compressive Strength			Average (PSI)
			PSI	Mpa	Kg/cm2	
1	2340	3	1957.5	13.5	115.4	2892.5
2	2346	3	1870	12.9	114.8	
3						
4	2355	7	2827.5	19.05	159.1	2864.47
5	2350	7	2901.45	20.01	162.2	
6						
7	2346	28	3335	23	224.4	3371
8	2354	28	3407	23.5	209.1	
9						

Prepared By: 	 بريكون للخرسانة والطابوق مختبر فحص المواد MATERIAL TESTING LAB PRECON CONCRETE & BLOCK	Checked By: 
--	--	--





بريكون  
للخرسانة والطابوق

## PRECON READY MIX & BLOCK

### Mix Design Report

Date:	01-01-2024	Mix Code:	1007
Client:	GENERAL		
Project:	GENERAL		

#### Mix Properties:

Strength:	6000 Psi (C40)	Min. Cement Content/m <sup>3</sup> :	420 kg	Cement Type:	I&V
W/C. Ratio	0.36	Max. Size of Agg.:	20 mm	Max. Slump:	140±40 mm

Ingredients	Sp. Gr. SSD	SSD Wt	% of Agg.	Volume/Lt	Source
Cement (Kg)	3.15	420		61.9	Saudi Cement
Micro Silica (Kg)	2.2				Al Rashed
Free Water (Lt)	1	155		180	Precon R/O Plant
Agg. 20mm (Kg)	2.578	650		267.6	Summan
Agg. 10mm (Kg)	2.573	410		151.6	Summan
Sand (Kg)	2.625	680		327.6	Local Dune
Admx-D-10 (L)	1.12	4.2		1.071428571	Fosam
Admx-G-62 (L)	1.13			0	
Admx-Lt.		0		0	
Air Content	%	2		20	
Total		2319		1000	

#### Fresh Concrete Properties:

Unit Wt Kg/M:	2319	Air Content:	2%	Slump:	150	Temp ©	25
Initial Setting Time (Min):		Final Setting Time(Mine):					

#### Harden Concrete Properties:

No.	Density (Kg/m)	Age (Days)	Compressive Strength			Average (PSI)
			PSI	Mpa	Kg/cm <sup>2</sup>	
1	2355	3	3915	27.0	275.4	3988
2	2356	3	4060	28.0	285.6	
3						
4	2359	7	5081	34.9	355.9	5141
5	2360	7	5220	36.0	367.2	
6						
7	2357	28	6946	47.0	488.6	6982
8	2359	28	7018	48.4	493.7	
9						

Prepared By: .....



Checked By: .....



بريكون  
للخرسانة والطابوق

## PRECON READY MIX & BLOCK Mix Design Report

Date:	01-01-2024	Mix Code:	1006
Client:	GENERAL		
Project:	GENERAL		

### Mix Properties:

Strength:	5500 Psi (C38)	Min. Cement Content/m <sup>3</sup> :	400 kg	Cement Type:	I&V
W/C. Ratio	0.38	Max. Size of Agg.:	20 mm	Max. Slump:	150±40 mm

Ingredients	Sp. Gr. SSD	SSD WT	%Of Agg	Volume/Lt	Source
Cement (Kg)	3.15	400		61.9	Saudi cement
Agg. 20mm (Kg)	2.578	665		267.6	Summan
Agg. 10mm (Kg)	2.573	430		151.6	Summan
Sand (Kg)	2.625	685		327.6	Local Dune
Admx-D-10 (L)	1.12	4		1.071428571	Fosam
Admx-G-62 (L)	1.13			0	Fosam
Free Water (Lt)	1	160		180	Precon R/o Planet
Air Content	%	2		20	
Total		2344		1000	

### Fresh Concrete Properties:

Unit Wt Kg/M:2344	Air Content: 2%	Slump: 150	Temp 25
Setting Time (Min):		Final Setting Time(Mine):	

### Harden Concrete Properties:

No.	Density (Kg/m)	Age (Days)	Compressive Strength			Average (PSI)
			PSI	Mpa	Kg/cm <sup>2</sup>	
1	2340	3	3510.45	24.21	119.22	3467.67
2	2346	3	3424.9	23.62	122.54	
3						
4	2355	7	4421.05	30.49	180.1	4514.52
5	2350	7	4608.1	31.78	190.2	
6						
7	2346	28	5638	38.88	396.39	5645
8	2354	28	5652	38.97	397.37	
9						

Prepared By: .....



Checked By: .....





بريكون  
للخرسانة والطابوق

## PRECON READY MIX & BLOCK

### Mix Design Report

Date:	01-01-2024	Mix Code:	1006
Client:	GENERAL		
Project:	GENERAL		

#### Mix Properties:

Strength:	5000 Psi (C35)	Min. Cement Content/m <sup>3</sup> :	360 kg	Cement Type:	I&V
W/C. Ratio	0.42	Max. Size of Agg.:	20 mm	Max. Slump:	140±40mm

Ingredients	Sp. Gr. SSD	SSD Wt	% of Agg.	Volume/Lt	Source
Cement (Kg)	3.15	380		61.9	Saudi Cement
Micro Silica (Kg)	2.2				Al Rashed
Free Water (Lt)	1	160		180	Precon R/O Plant
Agg. 20mm (Kg)	2.578	655		267.6	Summan
Agg. 10mm (Kg)	2.573	420		151.6	Summan
Sand (Kg)	2.625	690		327.6	Local Dune
Admx-D-10 (L)	1.12	3.8		1.071428571	Fosam
Admx-G-62 (L)	1.13			0	
Admx-Lt.		0		0	
Air Content	%	2		20	
Total		2308		1000	

#### Fresh Concrete Properties:

Unit Wt Kg/M:	2308	Air Content:	2%	Slump:	140	Temp ©	26
Initial Setting Time (Min):		Final Setting Time(Mine):					


#### Harden Concrete Properties:

No.	Density (Kg/m)	Age (Days)	Compressive Strength			Average (PSI)
			PSI	Mpa	Kg/cm <sup>2</sup>	
1	2340	3	3416.2	23.56	121.2	3256.7
2	2346	3	3097.2	21.36	133.4	
3						
4	2355	7	4844.45	33.41	170.1	4803.85
5	2350	7	4763.25	32.85	186.2	
6						
7	2346	28	5412.85	37.33	249.4	5388
8	2354	28	5363.55	36.99	265.1	
9						

Prepared By: .....



Checked By: .....



## PRECON READY MIX & BLOCK Mix Design Report

Date:	01-01-2024	Mix Code:	1005
Client:	GENERAL		
Project:	GENERAL		

### Mix Properties:

Strength:	4500 Psi (C30)	Min. Cement Content/m3:	330 kg	Cement Type:	I&V
W/C. Ratio	0.48	Max. Size of Agg.:	20 mm	Max. Slump:	140±40 mm

Ingredients	Sp. Gr. SSD	SSD Wt	% of Agg.	Volume/Lt	Source
Cement (Kg)	3.15	340		61.9	Saudi Cement
Micro Silica (Kg)	2.2				Al Rashed
Free Water (Lt)	1	165		180	Precon R/O Plant
Agg. 20mm (Kg)	2.578	656		267.6	Summan
Agg. 10mm (Kg)	2.573	426		151.6	Summan
Sand (Kg)	2.625	720		327.6	Local Dune
Admx-D-10 (L)	1.12	3.4		1.071428571	Fosam
Admx-G-62 (L)	1.13			0	
Admx-Lt.		0		0	
Air Content	%	2		20	
Total		2310		1000	

### Fresh Concrete Properties:

Unit Wt Kg/M:	2310	Air Content:	2%	Slump:	150	Temp ©	25
Initial Setting Time (Min):		Final Setting Time(Mine):					

### Harden Concrete Properties:


No.	Density (Kg/m)	Age (Days)	Compressive Strength			Average (PSI)
			PSI	Mpa	Kg/cm2	
1	2364	3	3451	23.8	242.8	3473
2	2357	3	3495	24.1	245.8	
3						
4	2362	7	4437	30.6	312.1	4466
5	2365	7	4495	31.0	316.2	
6						
7	2369	28	5510	38.0	387.6	5590
8	2370	28	5670	39.1	399.0	
9						


Prepared By: .....



Checked By: .....





 <b>بريكون</b> للخرسانة والطابوق	<b>PRECON READY MIX &amp; BLOCK</b> <b>Mix Design Report</b>		
Date:	01-01-2024	Mix Code:	1004
Client:	GENERAL		
Project:	GENERAL		

**Mix Properties:**

Strength:	4000 Psi (C28)	Min. Cement Content/m3:	320 kg	Cement Type:	OPC
W/C. Ratio	0.53	Max. Size of Agg.:	20 mm	Max. Slump:	140±40 mm

Ingredients	Sp. Gr. SSD	SSD Wt	% of Agg.	Volume/Lt	Source
Cement (Kg)	3.15	320		61.9	Saudi Cement
Micro Silica (Kg)	2.2				Al Rashed
Free Water (Lt)	1	170		180	Precon R/O Plant
Agg. 20mm (Kg)	2.578	660		267.6	Summan
Agg. 10mm (Kg)	2.573	450		151.6	Summan
Sand (Kg)	2.625	720		327.6	Local Dune
Admx-D-10 (L)	1.12	3.2		1.071428571	Fosam
Admx-G-62 (L)	1.13			0	
Admx-Lt.		0		0	
Air Content	%	2		20	
Total		2323		1000	


**Fresh Concrete Properties:**

Unit Wt Kg/M:	2323	Air Content:	2%	Slump:	145	Temp ©	25
Initial Setting Time (Min):		Final Setting Time(Mine):					

**Harden Concrete Properties:**

No.	Density (Kg/m)	Age (Days)	Compressive Strength			Average (PSI)
			PSI	Mpa	Kg/cm2	
1	2346	3	2494	17.2	175.4	2436
2	2360	3	2378	16.4	163.3	
3						
4	2366	7	3248	22.4	228.5	3256
5	2372	7	3263	22.5	229.5	
6						
7	2369	28	4408	30.4	310.1	4423
8	2370	28	4437	30.6	312.1	
9						

Prepared By: 	 بريكون للخرسانة والطابوق مختبر فحص المواد MATERIAL TESTING LAB PRECON CONCRETE & BLOCK	Checked By: 
--	--	--





## PRECON READY MIX & BLOCK Mix Design Report

Date:	01-01-2024	Mix Code:	1001
Client:	GENERAL		
Project:	GENERAL		

### Mix Properties:

Strength:	2500 Psi (C17)	Min. Cement Content/m3:	240 kg	Cement Type:	I&V
W/C. Ratio	0.75	Max. Size of Agg.:	20 mm	Max. Slump:	140+40 mm

Ingredients	Sp. Gr. SSD	SSD Wt	% of Agg.	Volume/Lt	Source
Cement (Kg)	3.15	240		61.9	Saudi Cement
Micro Silica (Kg)	2.2				Al Rashed
Free Water (Lt)	1	180		180	Precon R/O Plant
Agg. 20mm (Kg)	2.578	555		267.6	Summan
Agg. 10mm (Kg)	2.573	490		151.6	Summan
Sand (Kg)	2.625	850		327.6	Local Dune
Admx-D-10 (L)	1.12	2.4		1.071428571	Fosam
Admx-G-62 (L)	1.13			0	
Admx-Lt.		0		0	
Air Content	%	2		20	
Total		2317		1000	

### Fresh Concrete Properties:

Unit Wt Kg/M:	2317	Air Content:	2%	Slump:	160	Temp ©	25
Initial Setting Time (Min):		Final Setting Time(Mine):					

### Harden Concrete Properties:

No.	Density (Kg/m)	Age (Days)	Compressive Strength			Average (PSI)
			PSI	Mpa	Kg/cm2	
1	2340	3	1595	11.0	112.2	1668
2	2346	3	1740	12.0	122.4	
3						
4	2355	7	2262	15.6	159.1	2284
5	2350	7	2306	15.9	162.2	
6						
7	2346	28	3190	22.0	224.4	3081
8	2354	28	2973	20.5	209.1	
9						

Prepared By: .....



Checked By: .....





بريكون  
للخرسانة والطابوق

## PRECON READY MIX & BLOCK Mix Design Report

Date:	01-01-2024	Mix Code:	1003
Client:	GENERAL		
Project:	GENERAL		

### Mix Properties:

Strength:	3500 Psi (C25)	Min. Cement Content/m <sup>3</sup> :	290 kg	Cement Type:	I&V
W/C. Ratio	0.58	Max. Size of Agg.:	20 mm	Max. Slump:	140±40 mm

Ingredients	Sp. Gr. SSD	SSD Wt	% of Agg.	Volume/Lt	Source
Cement (Kg)	3.15	290		61.9	Saudi Cement
Micro Silica (Kg)	2.2				Al Rashed
Free Water (Lt)	1	170		180	Precon R/O Plant
Agg. 20mm (Kg)	2.578	667		267.6	Summan
Agg. 10mm (Kg)	2.573	438		151.6	Summan
Sand (Kg)	2.625	738		327.6	Local Dune
Admx-D-10 (L)	1.12	2.9		1.071428571	Fosam
Admx-G-62 (L)	1.13			0	
Admx-Lt.		0		0	
Air Content	%	2		20	
Total		2305		1000	

### Fresh Concrete Properties:

Unit Wt Kg/M:	2305	Air Content:	2%	Slump:	140	Temp ©	25
Initial Setting Time (Min):		Final Setting Time(Mine):					

### Harden Concrete Properties:

No.	Density (Kg/m)	Age (Days)	Compressive Strength			Average (PSI)
			PSI	Mpa	Kg/cm <sup>2</sup>	
1	2340	3	2175	15.0	112.2	2247
2	2346	3	2320	16.0	122.4	
3						
4	2355	7	3132	21.6	159.1	3226.25
5	2350	7	3320.5	22.9	162.2	
6						
7	2346	28	3770	26.0	224.4	3878.75
8	2354	28	3987	27.5	209.1	
9						

Prepared By: .....



Checked By: .....



# QA/AC DEPARTMENT

## Compressive Strength Test Report





QA/AC DEPARTMENT

Compressive Strength Test Report



بريكون  
للخرسانة والطابوق

Design Strength :	4000 PSI	Date:	6/3/2024
Mix Code :	SRC 4000	Lab No:	1
Mix No:	1	Cement Type:	4000 PSI 4000
Method :	ASTM C94	Admixture:	RP215

Client Name: Darat Al Khobar  
Site Location: Dallah

DETAILS OF CONCRETE SAMPLING & TEST

Sampling Data		Concrete Properties		Requirements
Date of Sampled	6-Mar-24	Slump(mm)	100	
Sampled by:	ROSHAN	Concrete Temp. (°C)	25	
Ticket No:	M 52	Ambient Temp. (°C)		-
Truck No:		Air Content (%)		-
Time of Sampling:		Unit Weight (Kg/m <sup>3</sup> )	2330.5	

Sampled At :		Type of Specimen		Size of Specimen	Area
Plant	NO	Cylinder	YES	300*150	17671.5
Site	YES	Cube	-		
		Beam	-		

Sample No.	Date of Test	Age of Sample	Load (KN)	Strength	
				Mpa	Psi
A	3-Apr-24	28 Day	675.54	30.12	4367.04
B	3-Apr-24	28 Day	670.34	29.08	4216.06
C	3-Apr-24	28 Day	672.42	29.54	4283.03
Average of Strength :					4289

Remarks : Foundation

Prepared By :

ROSHAN  
Q/C Technician

Checked By :

Ahmed Al Masri  
Q/C Manager



Rev. No:00; Date:18.07.2017; FM.QC.14



QA/AC DEPARTMENT  
Compressive Strength Test Report



Design Strength :	4000 PSI	Date:	25/12/2023
Mix Code :	SRC 4000	Lab No:	1
Mix No:	1	Cement Type:	4000 PSI 4000
Method :	ASTM C94	Admixture:	RP215

Client Name: Ramzy Al Ghamdy  
Site Location: Al Nada

DETAILS OF CONCRETE SAMPLING & TEST

Sampling Data		Concrete Properties		Requirements
Date of Sampled	25/12/2023	Slump(mm)	112	
Sampled by:	ROSHAN	Concrete Temp. (°C)	25	
Ticket No:		Ambient Temp. (°C)		-
Truck No:	M.52	Air Content (%)		-
Time of Sampling:		Unit Weight (Kg/m³)	2130.7	

Sampled At :		Type of Specimen		Size of Specimen	Area
Plant	NO	Cylinder	YES	300*150	17671.5
Site	YES	Cube	-		
		Beam	-		

Sample No.	Date of Test	Age of Sample	Load (KN)	Strength	
				Mpa	Psi
A	24/01/2024	28Day	666.28	29.60	4292.00
B	24/01/2024	28 Day	699.12	33.25	4821.25
C	24/01/2024	28 Day	667.25	29.66	4300.70
Average of Strength :					4471

Remarks :

Prepared By : ROSHAN Q/C Technician  
Checked By : Ahmed Al Masri Q/C Meneger



Rev.No.00; Date:18.07.2017; FM.QC.14





QA/AC DEPARTMENT

Compressive Strength Test Report



Design Strength :	4000 PSI	Date:	6/3/2024
Mix Code :	SRC 4000	Lab No:	1
Mix No:	1	Cement Type:	4000 PSI 4000
Method :	ASTM C94	Admixture:	RP215

Client Name: Darat Al Khobar  
Site Location: Dallah

DETAILS OF CONCRETE SAMPLING & TEST

Sampling Data		Concrete Properties		Requirements
Date of Sampled	6-Mar-24	Slump(mm)	100	
Sampled by:	ROSHAN	Concrete Temp. (°C)	25	
Ticket No:	M 52	Ambient Temp. (°C)		
Truck No:		Air Content (%)		
Time of Sampling:		Unit Weight (Kg/m <sup>3</sup> )	2330.5	

Sampled At :		Type of Specimen	Size of Specimen	Area
Plant	NO	Cylinder	YES	300*150
Site	YES	Cube	-	
		Beam	-	

Sample No.	Date of Test	Age of Sample	Load (KN)	Strength	
				Mpa	Psi
A	13/03/2024	07 Day	499.17	22.01	3145.45
B	13/03/2024	07 Day	523.67	23.03	3339.35
C	13/03/2024	07 Day	470.65	20.01	2901.46
Average of Strength :					3129

Remarks : Foundation

Prepared By : ROSHAN Q/C Technician  
Checked By : Ahmed Al Masri Q/C Manager



Rev.No.00; Date:18.07.2017; FM.QC.14



QA/AC DEPARTMENT  
Compressive Strength Test Report



Design Strength :	4000 PSI	Date:	5/11/2024
Mix Code :	SRC 4000	Lab No:	1
Mix No:	1	Cement Type:	4000 PSI 4000
Method :	ASTM C94	Admixture:	RP215

Client Name: Darat Al Khobar  
Site Location: Dallah

DETAILS OF CONCRETE SAMPLING & TEST


Sampling Data		Concrete Properties		Requirements
Date of Sampled	11-May-24	Slump(mm)	112	
Sampled by:	ROSHAN	Concrete Temp. (°C)	32	
Ticket No:	54	Ambient Temp. (°C)		
Truck No:		Air Content (%)		
Time of Sampling:		Unit Weight (Kg/m <sup>3</sup> )	2330.5	


Sampled At :		Type of Specimen		Size of Specimen	Area
Plant	NO	Cylinder	YES	300*150	17671.5
Site	YES	Cube	-		
		Beam	-		

Sample No.	Date of Test	Age of Sample	Load (KN)	Strength	
				Mpa	Psi
A	18/05/2024	07 Day	583.56	25.90	3755.50
B	18/05/2024	07 Day	536.65	23.08	3346.60
C	18/05/2024	07 Day	580.27	25.60	3712.00

Average of Strength : 3605

Remarks : Foundation

Prepared By:  ROSHAN  
Q/C Technician

Checked By:  Ahmed Al Masri  
Q/C Manager

Rev.No.00; Date:18.07.2017; FM.QC.14





QA/AC DEPARTMENT  
Compressive Strength Test Report



Design Strength :	4000 PSI	Date:	25/12/2023
Mix Code :	SRC 4000	Lab No:	1
Mix No:	1	Cement Type:	4000 PSI 4000
Method :	ASTM C94	Admixture:	RP215

Client Name: Ramzy Al Ghamdy  
Site Location: Al Nada

DETAILS OF CONCRETE SAMPLING & TEST

Sampling Data		Concrete Properties		Requirements
Date of Sampled	25/12/2023	Slump(mm)	112	
Sampled by:	ROSHAN	Concrete Temp. (°C)	25	
Ticket No:		Ambient Temp. (°C)		-
Truck No:	M.52	Air Content (%)		-
Time of Sampling:		Unit Weight (Kg/m <sup>3</sup> )	2130.7	

Sampled At :		Type of Specimen		Size of Specimen	Area
Plant	NO	Cylinder	YES	300*150	17671.5
Site	YES	Cube	-		
		Beam	-		

Sample No.	Date of Test	Age of Sample	Load (KN)	Strength	
				Mpa	Psi
A	1-Jan-24	07Day	583.56	25.90	3755.50
B	1-Jan-24	07 Day	536.65	23.08	3346.60
C	1-Jan-24	07 Day	546.04	24.02	3482.90
Average of Strength :					3528

Remarks :  
\_\_\_\_\_  
\_\_\_\_\_

Prepared By : ROSHAN Q/C Technician  
Checked By : Ahmed Al Masri Q/C Manager



Rev.No.00; Date:18.07.2017; FM.QC.14



## QA/AC DEPARTMENT

## Compressive Strength Test Report



Design Strength :	4000 PSI	Date:	3/6/2024
Mix Code :	OPC 4000	Lab No:	1
Mix No:	1	Cement Type:	4000 PSI 4000
Method :	ASTM C94	Admixture:	RP215

Client Name: Samri Contractind Company  
Site Location: Air Port

## DETAILS OF CONCRETE SAMPLING &amp; TEST

Sampling Data		Concrete Properties		Requirements
Date of Sampled	3-Jun-24	Slump(mm)	110	
Sampled by:	ROSHAN	Concrete Temp. (°C)	29	
Ticket No:		Ambient Temp. (°C)		-
Truck No:	7452	Air Content (%)		-
Time of Sampling:		Unit Weight (Kg/m <sup>3</sup> )	2130.7	

Sampled At :		Type of Specimen		Size of Specimen	Area
Plant	NO	Cylinder	YES	300*150	17671.5
Site	YES	Cube	-		
		Beam	-		

Sample No.	Date of Test	Age of Sample	Load (KN)	Strength	
				Mpa	Psi
A	10-Jun-24	07Day	472.69	21.00	3045.00
B	10-Jun-24	07 Day	476.12	21.10	3059.50
C	10-Jun-24	07 Day	493.2	21.90	3175.50

Average of Strength : 3093

Remarks : Foundation

Prepared By :

ROSHAN  
Q/C Technician

Checked By :


Ahmed Al Masri  
Q/C Manager

Rev.No.00; Date:18.07.2017; FM.QC.14





# Reports and calibrations



**BUILDING TRUST**



Sika Saudi Arabia- Rabigh Industrial City Phase 3 - 21371 Rabigh

CONTACT  
Ioan Bran  
R&D/QC Manager  
Phone: +966 56 908 0447  
Fax: +966 12 692 1272  
bran.ioan@sa.sika.com  
gcc.sika.com

To: **Abo Haitham Trading Group Co.**

Batch number: **DM-2406093**

Delivery number: **10936/24**

Product: **Sika Plast 160 Plus**

Reference: **0784 / 27.06.2024**

Dear Sir,  
Referring to above subject we confirm hereby the following:

### Inspection certificate


Nr.	Properties	QC Tests results	QC Specification	Test Method used
1.	Aspect	Light Brown Liquid	Light Brown Liquid	CQP 001 - 1 V.6
2.	Specific Gravity	1.037	1.020 - 1.060	CQP006-1 V.3
3.	Solid Content	15.67	14.00 - 17.00 %	CQP002-1 V.3
4.	pH	3.19	3.00 - 6.00	CQP004-1 V.4

**Ioan Bran**  
R&D/QC Manager



**Abdulaziz Alrabighi**  
QC. Engineer

Disclaimer: The above stated test results reflect the Products' properties when tested under laboratory conditions. Test methods used are state-of-art test methods commonly used for the products in question. In practice, the differences in materials, substrates and actual site conditions are such that no warranty in respect of merchantability or of fitness for a particular purpose, nor any liability arising out of any legal relationship whatsoever, can be inferred either from this information, or from any written recommendations, or from any other advice offered. The user of the product must test the product's suitability for the intended application and purpose. Sika Saudi Arabia Co Ltd. reserves the right to change the properties of its products. The proprietary rights of third parties must be observed. All orders are accepted subject to our current terms of sale and delivery. Users must always refer to the most recent issue of the local Product Data Sheet for the product concerned, copies of which will be supplied on request.



## Gulf Engineering House

### TEST REPORT

---

### COMPRESSIVE STRENGTH OF CONCRETE CYLINDER

<b>Client Name</b> : PRECON <b>Project Name</b> : MAJID ABU AL MAKARAM QATIF <b>Sample Source</b> : <b>Sample Description</b> : CONCRETE 4500 PSI, SRC <b>Sampling Method</b> : C31/C31M-21a,C172/172M-17 <b>Method of Placement</b> : <b>Sampled by</b> : CLIENT <b>Environmental Condition (Lab)</b> : Temp(°C): 23 Humidity(%): 55 <b>RFI No.</b> :	<b>Lab Ref. No.</b> : <b>Lab Project No.</b> : <b>Date Sampled</b> : 14-10-23 <b>Date Sample Received</b> : 16-12-23 <b>Date Reported</b> : 16-12-23 <b>Tested by</b> : HASSAN <b>Test Location</b> : DAMMAM LAB	<b>Email</b> : <b>Compressive Strength</b> PSI : 5427 MPa : 37.4 U : + 0.2 <b>Average 28 Days (Lab)</b> : 37.4	<b>Type of Fracture</b> : T-2 <b>Remarks</b> : PASSED <b>Type of Curing</b> : Lab
--	--	---	---

Sample No.	Date Tested (days)	Age (days)	Dimension (mm)	Area (mm <sup>2</sup> )	Weight (g)	Density (kg/m <sup>3</sup> )	Air Content (%)	Slump (mm)	Dial Reading (kN)	Kg/cm <sup>2</sup>	PSI	MPa	Remarks	Type of Fracture
1	16-12-23	<28	15 x 30	176.7	12330	2326	-	-	661.3	381.6	5427	37.4	PASSED	T-2
<b>Average 28 Days (Lab)</b>											37.4	37.4	PASSED	

**Time Batched (Hrs.):** \_\_\_\_\_  
**Time Sampled (Hrs.):** \_\_\_\_\_  
**Location & Structure:** COLUMN

**Test Method:** ASTM C39/C39M-21      **Method Variation:** NIL

**Reference Specifications/Standards for Statement of Conformity:** NIL

**Statement of Conformity:**  Passed     Failed


**Decision Rule:** The statement of conformity is related to test results only, regardless of the uncertainty calculations.

**Remarks:** Sampling Information Provided by Client. Sample received for compressive strength testing only.

**Notes:** (1) The stated expanded uncertainty of measurement is the combined uncertainty of measurements multiplied by the coverage factor k=2, providing a level of confidence approximately 95%.  
 (2) The above results are related to the tested sample/specimen only.  
 (3) This test report shall not be reproduced except in full, without a written approval from GEH Dammam Laboratory.  
 (4) Expanded Uncertainty = U


**Reviewed By** : S.M.ANAS/CTTA #0825 (Lab Supervisor)  
 P.O.Box, 3569, Dammam, 31481, KSA. T. +966 13 8210415  
 F. +966 13 8210412. Email: admin-dam@ataulab.com

**Approved By** : FERAS/CTTA #0326 (Tech. Supervisor)  
 Date : April 2023  
 Page : 1 of 1



Issue No. : 4  
 Document No. : 1016/0326/2023

This test is accredited by ISO/IEC 17025.



## Gulf Engineering House

### TEST REPORT

#### COMPRESSIVE STRENGTH OF CONCRETE CYLINDER

<b>Client Name</b> : PRECON <b>Project Name</b> : MAJID ABU AL MAKARAM <b>Sample Source</b> : CONCRETE 4500 PSI, SRC <b>Sampling Method</b> : C31/C31M-2.1a, C172/172M-17 <b>Method of Placement</b> : <b>Sampled by</b> : CLIENT <b>Environmental Condition (Lab)</b> : Temp(°C): 23 Humidity(%): 55 Curing Temp(°C): 23±2 <b>RFI No.</b> :	<b>Email</b> : <b>Lab Ref. No.</b> : <b>Lab Project No.</b> : <b>Date Sampled</b> : 16-11-23 <b>Date Sample Received</b> : 16-12-23 <b>Date Reported</b> : 16-12-23 <b>Tested by</b> : SAIDU/CITTA#834 <b>Test Location</b> : DAMMAM LAB	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th rowspan="2">Sample No.</th> <th rowspan="2">Date Tested (days)</th> <th rowspan="2">Age (days)</th> <th rowspan="2">Dimension (mm)</th> <th rowspan="2">Area (mm<sup>2</sup>)</th> <th rowspan="2">Weight (g)</th> <th rowspan="2">Density (kg/m<sup>3</sup>)</th> <th rowspan="2">Air Content (%)</th> <th rowspan="2">Slump (mm)</th> <th rowspan="2">Dial Reading (KN)</th> <th colspan="2">Compressive Strength</th> <th rowspan="2">Type of Fracture</th> <th rowspan="2">Remarks</th> <th rowspan="2">Type of Curing</th> </tr> <tr> <th>MPa</th> <th>PSI</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>16-12-23</td> <td>&lt;28</td> <td>15 x 30</td> <td>176.7</td> <td>12719</td> <td>2399</td> <td>-</td> <td>-</td> <td>569.9</td> <td>328.8</td> <td>32.2</td> <td>+ 0.2</td> <td>T-5</td> <td>PASSED</td> <td>Lab</td> </tr> <tr> <td>2</td> <td>16-12-23</td> <td>&lt;28</td> <td>15 x 30</td> <td>176.7</td> <td>12311</td> <td>2322</td> <td>-</td> <td>-</td> <td>585.3</td> <td>337.7</td> <td>33.1</td> <td>+ 0.2</td> <td>T-2</td> <td>PASSED</td> <td>Lab</td> </tr> <tr> <td colspan="10" style="text-align: center;"><b>Average 28 Days (Lab)</b></td> <td>333.3</td> <td>4740</td> <td>32.7</td> <td>-</td> <td>-</td> <td>-</td> </tr> </tbody> </table>	Sample No.	Date Tested (days)	Age (days)	Dimension (mm)	Area (mm <sup>2</sup> )	Weight (g)	Density (kg/m <sup>3</sup> )	Air Content (%)	Slump (mm)	Dial Reading (KN)	Compressive Strength		Type of Fracture	Remarks	Type of Curing	MPa	PSI	1	16-12-23	<28	15 x 30	176.7	12719	2399	-	-	569.9	328.8	32.2	+ 0.2	T-5	PASSED	Lab	2	16-12-23	<28	15 x 30	176.7	12311	2322	-	-	585.3	337.7	33.1	+ 0.2	T-2	PASSED	Lab	<b>Average 28 Days (Lab)</b>										333.3	4740	32.7	-	-	-
Sample No.	Date Tested (days)	Age (days)											Dimension (mm)	Area (mm <sup>2</sup> )				Weight (g)	Density (kg/m <sup>3</sup> )	Air Content (%)	Slump (mm)	Dial Reading (KN)	Compressive Strength		Type of Fracture	Remarks	Type of Curing																																								
			MPa	PSI																																																															
1	16-12-23	<28	15 x 30	176.7	12719	2399	-	-	569.9	328.8	32.2	+ 0.2	T-5	PASSED	Lab																																																				
2	16-12-23	<28	15 x 30	176.7	12311	2322	-	-	585.3	337.7	33.1	+ 0.2	T-2	PASSED	Lab																																																				
<b>Average 28 Days (Lab)</b>										333.3	4740	32.7	-	-	-																																																				

**Time Batched (Hrs.):** \_\_\_\_\_  
**Time Sampled (Hrs.):** \_\_\_\_\_  
**Location & Structure:** SLAB

**Test Method:** ASTM C39/C39M-21  
**Method Variation:** NIL

**Reference Specifications/Standards for Statement of Conformity:** NIL

**Statement of Conformity:**  Passed  Failed  
 The statement of conformity is related to test results only, regardless of the uncertainty calculations.

**Decision Rule:** The statement of conformity is related to test results only, regardless of the uncertainty calculations.


**Remarks:** Sampling information Provided by Client. Sample received for compressive strength testing only


**Notes:** (1) The stated expanded uncertainty of measurement is the combined uncertainty of measurements multiplied by the coverage factor k=2, providing a level of confidence approximately 95%.  
 (2) The above results are related to the tested sample/specimen only.  
 (3) This test report shall not be reproduced except in full, without a written approval from GEH Dammam Laboratory.  
 (4) Expanded Uncertainty = U

S.MANAS/ CTTA #0825 (Lab Supervisor)

Reviewed By

P.O. Box: 31659, Dammam-31461- KSA, T: +966 132710415  
F: +966 13 0210412, Email: gmanas@geh.com


  
 MATERIAL TESTING LAB  
 PRECON CONCRETE B B BLOCK

  
 Gulf Engineering House  
 100366 Health Substation

Approved By \_\_\_\_\_  
 Date: April 2023  
 Page: 1 of 1

This test is accredited by ISO/IEC 17025.





## Gulf Engineering House

### TEST REPORT

---

### COMPRESSIVE STRENGTH OF CONCRETE CYLINDER

Client Name : PRECON  
 Project Name : MAJID ABU AL MAKARAM QATIF  
 Sample Source : -  
 Sample Description : CONCRETE 4500 PSI, SRC  
 Sampling Method : C31/C31M-21a, C172.172M-17  
 Method of Placement : -  
 Sampled by : CLIENT  
 Environmental Condition (Lab) : Temp(°C): 23 Humidity(%): 55  
 RFI No. : Curing Temp(°C): 23±2

Email : -  
 Lab Ref. No. : -  
 Lab Project No. : -  
 Date Sampled : 02-10-23  
 Date Sample Received : -  
 Date Reported : 16-12-23  
 Tested by : HASSAN  
 Test Location : DAMMAM LAB

Sample No.	Date Tested	Age (days)	Dimension (mm)	Area (mm <sup>2</sup> )	Weight (g)	Density (kg/m <sup>3</sup> )	Air Content (%)	Slump (mm)	Dial Reading (kN)	Compressive Strength			Type of Fracture	Remarks	Type of Curing
										Kg/cm <sup>2</sup>	MPa	U			
1	16-12-23	<28	15 x 30	176.7	12526	2363	-	-	830.3	479.1	6814	+ 0.2	T-2	PASSED	Lab
2	16-12-23	<28	15 x 30	176.7	12846	2385	-	-	826.3	476.8	6781	+ 0.2	T-3	PASSED	Lab
Average 28 Days (Lab)										477.9	6798	-	-	PASSED	-

Ticket/ Batch No.:  
 Temperature of Mix (°C):

Time Batched (Hrs.):  
 Time Sampled (Hrs.):  
 Location & Structure: Wall

---

Test Method: ASTM C39/C39M-21      Method Variation: NIL

Reference Specifications/Standards for Statement of Conformity: NIL

Statement of Conformity:  Passed     Failed

Decision Rule: The statement of conformity is related to test results only, regardless of the uncertainty calculations.

Remarks: Sampling Information Provided by Client. Sample received for compressive strength testing only


---

**END OF RESULTS**

Notes: (1) The stated expanded uncertainty of measurement is the combined uncertainty of measurements multiplied by the coverage factor k=2, providing a level of confidence approximately 95%.  
 (2) The above results are related to the tested sample/specimen only.  
 (3) This test report shall not be reproduced except in full, without a written approval from GEH Dammam Laboratory.  
 (4) Expanded Uncertainty = U

S.M./ANAS/ CTTA #0825 (Lab Supervisor)  
 Reviewed By

P.O. Box: 3589, Dammam-31481-K.S.A. T. +966 13 8210415.  
 F. +966 13 8210412. Email: admin-dam@darahajj.com




Approved By


Date: April 2023

Page: 1 of 1

This test is accredited by ISO/IEC 17025



C.P.N.: 1010515504 (Techn. Supervisor)  
 FERAS/07747/0320 (Techn. Supervisor)



## Gulf Engineering House

### TEST REPORT

#### COMPRESSIVE STRENGTH OF CONCRETE CYLINDER

<b>Client Name</b> : PRECON <b>Project Name</b> : MAJID ABU AL MAKARAM <b>Sample Source</b> : - <b>Sample Description</b> : CONCRETE 400 PSI <b>Sampling Method</b> : C31/C31M-21a.C172/172M-17 <b>Method of Placement</b> : - <b>Sampled by</b> : - <b>Environmental Condition (Lab)</b> : Temp(°C): 23 Humidity(%): 55 Curing Temp(°C): 23±2 <b>RFI No.</b> :	<b>Email</b> : - <b>Lab Ref. No.</b> : - <b>Lab Project No.</b> : - <b>Date Sampled</b> : 26-08-23 <b>Date Sample Received</b> : - <b>Date Reported</b> : 25-09-23 <b>Tested by</b> : SHIJO/CTTA#1504 <b>Test Location</b> : DAMMAM LAB
---	--

Sample No.	Date Tested	Age (days)	Dimension (mm)	Area (mm <sup>2</sup> )	Weight (g)	Density (kg/m <sup>3</sup> )	Air Content (%)	Slump (mm)	Dial Reading (kN)	Compressive Strength			Type of Fracture	Remarks	Type of Curing
										Kg/cm <sup>2</sup>	PSI	MPa			
1	24-09-23	29	15 x 30	176.7	1269.1	2394	-	-	742.3	428.3	± 0.2	T-2	PASSED	Lab	
2	24-09-23	29	15 x 30	176.7	1246.2	2349	-	-	693.7	400.3	± 0.2	T-5	PASSED	Lab	
Average 29 Days (Lab)										414.3	5892	40.6			

**Time Batched (Hrs.):** \_\_\_\_\_  
**Time Sampled (Hrs.):** \_\_\_\_\_  
**Location & Structure:** \_\_\_\_\_

**Test Method:** ASTM C39/C39M-21      **Method Variation:** NIL

**Reference Specifications/Standards for Statement of Conformity:** NIL

**Statement of Conformity:**  Passed     Failed

**Decision Rule:** The statement of conformity is related to test results only, regardless of the uncertainty calculations.

**Remarks:** Sampling Information Provided by Client

**Notes:** (1) The stated expanded uncertainty of measurement is the combined uncertainty of measurements multiplied by the coverage factor k=2, providing a level of confidence approximately 95%.  
 (2) The above results are related to the tested sample/specimen only.  
 (3) This test report shall not be reproduced except in full, without a written approval from GEH Dammam Laboratory.  
 (4) Expanded Uncertainty = U


**Reviewed By**  
S.M.ANASI/CTTA #0825 (Lab Supervisor)

P.O.Box-3569 Dammam-31461- KSA. T. +966 13 8210415.  
F. +966 13 8210412. Email: abhin-jam@arabjail.com

**Approved By**  
Date: April 2023

Page: 1 of 1

This test is accredited by ISO/IEC 17025.



Dammam Lab. المملكة العربية السعودية  
Dammam Lab. المملكة العربية السعودية  
FERAS CENTER # 102405 (Dammam)



**AL-HOTY CALIBRATION SERVICES**  
A BRANCH OF AL-HOTY CO. LTD.

Calibration Laboratory  
C.R.2051015391  
25<sup>th</sup> Corner Zulfi St, Thuqbah,  
Al-Khobar 31952 - Kingdom of Saudi Arabia  
Tel. : (013) 864 4150 / 894 8020 / 894 5452  
Fax : (013) 898 1644 / 894 3980  
E-mail : [acs.kh@al-hoty.com](mailto:acs.kh@al-hoty.com)  
Website: [www.alhotycalibration.com](http://www.alhotycalibration.com)



## Certificate of Calibration

Certificate No: 12406010

**Customer Name:** Al Hisan Factory  
**Address:** Dammam, Kingdom of Saudi Arabia

**Product Identification and Specification**

Item Submitted:	Cement Scale	Page No:	1 of 2
Manufacturer:	Changsha Supmeter Technological Co Ltd.	Received Date:	01 June 2024
Model:	BST-106-B60S [L]	Calibration Date:	01 June 2024
Serial Number:	LX016256S	Calibration Due Date:	01 June 2025
Asset Number:	N/A	Certificate Issue Date:	06 June 2024
Customer P.O:	N/A	Received Condition:	In tolerance
		Returned Condition:	In tolerance

**Calibration Procedure:** ICP-I-071

**Summary of Procedure:** The Unit Under Test (UUT), an cement scale was carried-out by build-up test method using known weights with material or other product used during production. The test weights were placed onto the hopper and reading was then taken from the scale / indicator.

**Environmental Condition:** 42.4 ±0.6°C / 19.9 ±0.7%RH

**Calibration Results:** (see the next page)

**Calibration Notes:**

*Basis of Tolerance: ASTM C94/C94M-23*


*Max. Capacity: 3,000 kg / Resolution: 1 kg*

*Location: Plant # 2, Abu Hadiya, Dammam*


*The statement of compliance was based on the performance of the unit under test (UUT) against ASTM C94/C94M-23 requirements and taking the measurement uncertainty into account applies decision rule by metrological analysis.*

**Standard Used to Calibrate Instrument:**


Description	ACS Number	Cal Due Date	Traceability
Test Weights	ACS-KH-MA003	23 September 2024	1S240325 (NMCC, KSA / METAS)
Digital Temperature Humidity Meter	ACS-KH-TE025	15 April 2025	1S240415 (NIST, USA / NMCC, KSA)

Calibrated By:   
Calibration Tech. (Stamp)



Approved By:   
Manager

The reported expanded uncertainty of measurement is stated as the standard uncertainty measurement multiplied by the coverage factor k=2, providing a level of confidence of approximately 95%.  
This certifies that the above listed instrument has been calibrated using standards whose accuracies are traceable to national or international standards and in accordance with the quality system conform to ISO/IEC 17025:2017.



## AL-HOTY CALIBRATION SERVICES

Cement Scale  
Serial Number: LX016256S

Certificate Number: 12406010  
Page: 2 of 2

### Calibration Results

Test Description	Applied Load (kg)	UUT Reading (kg)		Error (kg)	Tolerance (kg)	Uncertainty (kg)	Compliance
		As found	As left				
Scale Accuracy	100	100	100	0	± 5	± 0.58	P
Test	200	200	200	0	± 5	± 0.58	P
	400	400	400	0	± 5	± 0.58	P
	600	599	599	-1	± 5	± 0.58	P
	800	801	801	+1	± 5	± 0.59	P
	1000	1001	1001	+1	± 5	± 0.59	P
	1200	1201	1201	+1	± 5	± 0.60	P
	1400	1399	1399	-1	± 5	± 0.60	P
	1600	1598	1598	-2	± 5	± 0.61	P

**Notation:**

- P - Pass
- \* P - Conditional Pass
- \* F - Conditional Fail
- F - Fail

End of Certificate





**AL-HOTY CALIBRATION SERVICES**  
A BRANCH OF AL-HOTY CO. LTD.

Calibration Laboratory  
C.R.2051015391  
25<sup>th</sup> Corner Zulfi St, Thuqbah,  
Al-Khobar 31952 - Kingdom of Saudi Arabia  
Tel. : (013) 864 4150 / 894 8020 / 894 5452  
Fax : (013) 898 1644 / 894 3980  
E-mail : [acs.kh@al-hoty.com](mailto:acs.kh@al-hoty.com)  
Website: [www.alhoty Calibration.com](http://www.alhoty Calibration.com)



## Certificate of Calibration

Certificate No: 12406011

**Customer Name:** Al Hisan Factory  
**Address:** Dammam, Kingdom of Saudi Arabia

### Product Identification and Specification

Item Submitted: Water Meter  
Manufacturer: EMKO  
Model: EZM-9930  
Serial Number: 31066642-W  
Asset Number: N/A  
Customer P.O: N/A

Page No: 1 of 2  
Received Date: 01 June 2024  
Calibration Date: 01 June 2024  
Calibration Due Date: 01 June 2025  
Certificate Issue Date: 06 June 2024  
Received Condition: In tolerance  
Returned Condition: In tolerance

**Calibration Procedure:** ICP-I-078

**Summary of Procedure:** The Unit Under Test (UUT), a water meter was calibrated by measuring the actual output water using a volumetric graduated container.

**Environmental Condition:** 42.2 ±1.0°C / 21.0 ±0.87%RH

**Calibration Results:** (see the next page)


### Calibration Notes:

*Basis of Tolerance: ASTM C94/C94M-23  
Max. Capacity: 999 Liters / Min. Division: 1L x7.5 Liters  
Location: Plant # 2, Abu Hadiya, Dammam  
The statement of compliance was based on the performance of the unit under test (UUT) against ASTM C94/C94M-23 requirements and taking the measurement uncertainty into account applies decision rule by metrological analysis.*

### Standard Used to Calibrate Instrument:

Description	ACS Number	Cal Due Date	Traceability
Volumetric Graduated Container	ACS-KH-FV008A	23 July 2024	1S240117 (METAS/NMCC, KSA/NIST, USA)
Digital Temperature Humidity Meter	ACS-KH-TE025	15 April 2025	1S240415 (NIST, USA / NMCC, KSA)

Calibrated By:   
Calibration Tech. (Stamp)

Approved By:   
Manager

The reported expanded uncertainty of measurement is stated as the standard uncertainty measurement multiplied by the coverage factor k=2, providing a level of confidence of approximately 95%.  
This certifies that the above listed instrument has been calibrated using standards whose accuracies are traceable to national or international standards and in accordance with the quality system conform to ISO/IEC 17025:2017.



## AL-HOTY CALIBRATION SERVICES

Water Meter	Certificate Number	12406011
Serial Number: 31066642-W	Page:	2 of 2

### Calibration Results



Test	UUT Setting	Nominal (liters)	Measured Output (liters)	Error (liters)	Tolerance (liters)	Uncertainty (liters)	Compliance
Description							
Meter Accuracy	27 (x 7.5)	202.5	200	-2.5	± 3	± 4.4	*P
Test							

#### Notation:

- P - Pass
- \* P - Conditional Pass
- \* F - Conditional Fail
- F - Fail

End of Certificate





## AL-HOTY CALIBRATION SERVICES

A BRANCH OF AL-HOTY CO. LTD.

Calibration Laboratory  
C.R.2051015391  
25<sup>th</sup> Corner Zulfi St, Thuqbah,  
Al-Khobar 31952 - Kingdom of Saudi Arabia  
Tel. : (013) 864 4150 / 894 8020 / 894 5452  
Fax : (013) 898 1644 / 894 3980  
E-mail : [acs.kh@al-hoty.com](mailto:acs.kh@al-hoty.com)  
Website: [www.alhotycalibration.com](http://www.alhotycalibration.com)



# Certificate of Calibration

Certificate No: 12406009

**Customer Name:** Al Hisan Factory  
**Address:** Dammam, Kingdom of Saudi Arabia

### Product Identification and Specification

Item Submitted:	Aggregate Scale	Page No:	1 of 2
Manufacturer:	Changsha Supmeter Technological Co Ltd.	Received Date:	01 June 2024
Model:	BST-106-B60S [L]	Calibration Date:	01 June 2024
Serial Number:	LX016255S	Calibration Due Date:	01 June 2025
Asset Number:	N/A	Certificate Issue Date:	06 June 2024
Customer P.O.:	N/A	Received Condition:	Out of tolerance
		Returned Condition:	Adjusted, in tolerance

**Calibration Procedure:** ICP-I-071

**Summary of Procedure:** The Unit Under Test (UUT), an aggregate scale was carried-out by build-up test method using known weights with material or other product used during production. The test weights were placed onto the hopper and reading was then taken from the scale / indicator.

**Environmental Condition:** 42.9 ±0.8°C / 20.6 ±0.5%RH

**Calibration Results:** (see the next page)

### Calibration Notes:

*Basis of Tolerance: ASTM C94/C94M-23  
Max. Capacity: 6,000 kg / Resolution: 1 kg  
Location: Plant # 2, Abu Hadriya, Dammam  
The statement of compliance was based on the performance of the unit under test (UUT) against ASTM C94/C94M-23 requirements and taking the measurement uncertainty into account applies decision rule by metrological analysis.*

### Standard Used to Calibrate Instrument:

Description	ACS Number	Cal Due Date	Traceability
Test Weights	ACS-JB-150	17 September 2024	1S240315 (METAS)
Test Weights	ACS-KH-MA003	23 September 2024	1S240325 (NMCC, KSA METAS)
Digital Temperature Humidity Meter	ACS-KH-TE025	15 April 2025	1S240415 (NIST, USA / NMCC, KSA)

Calibrated By: \_\_\_\_\_  
Calibration Tech. (Stamp)



Approved By: \_\_\_\_\_  
Manager

The reported expanded uncertainty of measurement is stated as the standard uncertainty measurement multiplied by the coverage factor k=2, providing a level of confidence of approximately 95%.  
This certifies that the above listed instrument has been calibrated using standards whose accuracies are traceable to national or international standards and in accordance with the quality system conform to ISO/IEC 17025:2017.



## AL-HOTY CALIBRATION SERVICES

Aggregate Scale  
Serial Number: LX016255S

Certificate Number: 12406009  
Page: 2 of 2


### Calibration Results

Test Description	Applied Load (kg)	UUT Reading (kg)		Error (kg)	Tolerance (kg)	Uncertainty (kg)	Compliance
		As found	As left				
Scale Accuracy	500	475	500	0	± 9	± 0.58	P
Test	1000	-	1000	0	± 9	± 0.59	P
	1500	-	1500	0	± 9	± 0.61	P
	2000	-	2000	0	± 9	± 0.63	P
	2500	-	2500	0	± 9	± 0.66	P
	3000	-	3000	0	± 9	± 0.69	P
	3500	-	3501	+1	± 9	± 0.73	P
	4000	-	4001	+1	± 9	± 0.77	P
	4500	-	4502	+1	± 9	± 0.82	P
	5000	-	5002	+2	± 9	± 0.86	P

#### Notation:

- P - Pass
- \* P - Conditional Pass
- \* F - Conditional Fail
- F - Fail

End of Certificate







**AL-HOTY CALIBRATION SERVICES**  
A BRANCH OF AL-HOTY CO. LTD.

Calibration Laboratory  
C.R.2051015391  
25<sup>th</sup> Corner Zulfi St, Thuqbah,  
Al-Khobar 31952 - Kingdom of Saudi Arabia  
Tel. : (013) 864 4150 / 894 8020 / 894 5452  
Fax : (013) 898 1644 / 894 3980  
E-mail : [acs.kh@al-hoty.com](mailto:acs.kh@al-hoty.com)  
Website: [www.alhoty Calibration.com](http://www.alhoty Calibration.com)



## Certificate of Calibration

Certificate No: 12406006

**Customer Name:** Al Hisan Factory  
**Address:** Dammam, Kingdom of Saudi Arabia

**Product Identification and Specification**

Item Submitted:	Aggregate Scale	Page No:	1 of 2
Manufacturer:	Changsha Supmeter Technological Co Ltd.	Received Date:	01 June 2024
Model:	BST-106-B60S [L]	Calibration Date:	01 June 2024
Serial Number:	LX016253S	Calibration Due Date:	01 June 2025
Asset Number:	N/A	Certificate Issue Date:	06 June 2024
Customer P.O.:	N/A	Received Condition:	In tolerance
		Returned Condition:	In tolerance

**Calibration Procedure:** ICP-I-071

**Summary of Procedure:** The Unit Under Test (UUT), an aggregate scale was carried-out by build-up test method using known weights with material or other product used during production. The test weights were placed onto the hopper and reading was then taken from the scale / indicator.

**Environmental Condition:** 43.6 ±0.5°C / 21.1 ±0.9%RH


**Calibration Results:** (see the next page)


**Calibration Notes:**

*Basis of Tolerance: ASTM C94/C94M-23  
Max. Capacity: 6,000 kg / Resolution: 1 kg  
Location: Plant # 1, Abu Hadriya, Dammam  
The statement of compliance was based on the performance of the unit under test (UUT) against ASTM C94/C94M-23 requirements and taking the measurement uncertainty into account applies decision rule by metrological analysis.*

**Standard Used to Calibrate Instrument:**

Description	ACS Number	Cal Due Date	Traceability
Test Weights	ACS-JB-150	17 September 2024	1S240315 (METAS)
Test Weights	ACS-KH-MA003	23 September 2024	1S240325 (NMCC, KSA METAS)
Digital Temperature Humidity Meter	ACS-KH-TE025	15 April 2025	1S240415 (NIST, USA / NMCC, KSA)

Calibrated By:   
Calibration Tech. (Stamp)

Approved By:   
Manager

The reported expanded uncertainty of measurement is stated as the standard uncertainty measurement multiplied by the coverage factor k=2, providing a level of confidence of approximately 95%.  
This certifies that the above listed instrument has been calibrated using standards whose accuracies are traceable to national or international standards and in accordance with the quality system conform to ISO/IEC 17025:2017.



## AL-HOTY CALIBRATION SERVICES

Aggregate Scale  
Serial Number: LX016253S

Certificate Number: 12406006  
Page: 2 of 2

### Calibration Results

Test Description	Applied Load (kg)	UUT Reading (kg)		Error (kg)	Tolerance (kg)	Uncertainty (kg)	Compliance
		As found	As left				
Scale Accuracy	500	500	500	0	± 9	± 0.58	P
Test	1000	1000	1000	0	± 9	± 0.59	P
	1500	1501	1501	1	± 9	± 0.61	P
	2000	2001	2001	1	± 9	± 0.63	P
	2500	2501	2501	1	± 9	± 0.66	P
	3000	3002	3002	2	± 9	± 0.69	P
	3500	3502	3502	2	± 9	± 0.73	P
	4000	4002	4002	2	± 9	± 0.77	P
	4500	4502	4502	2	± 9	± 0.82	P
	5000	5003	5003	3	± 9	± 0.86	P

**Notation:**

- P - Pass
- \* P - Conditional Pass
- \* F - Conditional Fail
- F - Fail

End of Certificate





## AL-HOTY CALIBRATION SERVICES

A BRANCH OF AL-HOTY CO. LTD.

Calibration Laboratory  
C.R.2051015391  
25<sup>th</sup> Corner Zulfi St, Thuqbah,  
Al-Khobar 31952 - Kingdom of Saudi Arabia  
Tel. : (013) 864 4150 / 894 8020 / 894 5452  
Fax : (013) 898 1644 / 894 3980  
E-mail : [acs.kh@al-hoty.com](mailto:acs.kh@al-hoty.com)  
Website: [www.alhoty Calibration.com](http://www.alhoty Calibration.com)



# Certificate of Calibration

Certificate No: 12406007

**Customer Name:** Al Hisan Factory  
**Address:** Dammam, Kingdom of Saudi Arabia

### Product Identification and Specification

Item Submitted: Cement Scale  
Manufacturer: -  
Model: TL6D MT0V2S0AC  
Serial Number: 22092701  
Asset Number: N/A  
Customer P.O: N/A

Page No: 1 of 2  
Received Date: 01 June 2024  
Calibration Date: 01 June 2024  
Calibration Due Date: 01 June 2025  
Certificate Issue Date: 06 June 2024  
Received Condition: In tolerance  
Returned Condition: In tolerance

**Calibration Procedure:** ICP-I-071

**Summary of Procedure:** The Unit Under Test (UUT), a cement scale was carried-out by build-up test method using known weights with material or other product used during production. The test weights were placed onto the hopper and reading was then taken from the scale / indicator.

**Environmental Condition:** 43.1 ±0.8°C / 20.6 ±0.4%RH

**Calibration Results:** (see the next page)

### Calibration Notes:

*Basis of Tolerance: ASTM C94/C94M-23*

*Max. Capacity: 2,500 kg / Resolution: 0.01 kg*

*Location: Plant # 1, Abu Hadiya, Dammam*


*The statement of compliance was based on the performance of the unit under test (UUT) against ASTM C94/C94M-23 requirements and taking the measurement uncertainty into account applies decision rule by metrological analysis.*

### Standard Used to Calibrate Instrument:

Description	ACS Number	Cal Due Date	Traceability
Test Weights	ACS-KH-MA003	23 September 2024	1S240325 (NMCC, KSA METAS)
Digital Temperature Humidity Meter	ACS-KH-TE025	15 April 2025	1S240415 (NIST, USA / NMCC, KSA)

Calibrated By: \_\_\_\_\_

Calibration Tech. (Stamp)




Approved By: \_\_\_\_\_

Manager

The reported expanded uncertainty of measurement is stated as the standard uncertainty measurement multiplied by the coverage factor k=2, providing a level of confidence of approximately 95%.

This certifies that the above listed instrument has been calibrated using standards whose accuracies are traceable to national or international standards and in accordance with the quality system conform to ISO/IEC 17025:2017.

This certificate applies only to the item described. Calibration certificates without signature and stamp are invalid.



## AL-HOTY CALIBRATION SERVICES

Cement Scale	Certificate Number: 12406007
Serial Number: 22092701	Page: 2 of 2

### Calibration Results

Test Description	Applied Load (kg)	UUT Reading (kg)		Error (kg)	Tolerance (kg)	Uncertainty (kg)	Compliance
		As found	As left				
Scale Accuracy	100	100.52	100.52	+0.52	± 4	± 0.0064	P
Test	200	200.61	200.61	+0.61	± 4	± 0.0079	P
	400	400.69	400.69	+0.69	± 4	± 0.052	P
	600	600.74	600.74	+0.74	± 4	± 0.077	P
	800	800.89	800.89	+0.89	± 4	± 0.10	P
	1000	1000.95	1000.95	+0.95	± 4	± 0.13	P
	1200	1201.19	1201.19	+1.19	± 4	± 0.15	P
	1400	1401.29	1401.29	+1.29	± 4	± 0.18	P
	1600	1601.38	1601.38	+1.38	± 4	± 0.21	P

#### Notation:

- P - Pass
- \* P - Conditional Pass
- \* F - Conditional Fail
- F - Fail

End of Certificate





## AL-HOTY CALIBRATION SERVICES

A BRANCH OF AL-HOTY CO. LTD.

Calibration Laboratory  
C.R.2051015391  
25<sup>th</sup> Corner Zulfi St, Thuqbah,  
Al-Khobar 31952 - Kingdom of Saudi Arabia  
Tel. : (013) 864 4150 / 894 8020 / 894 5452  
Fax : (013) 898 1644 / 894 3980  
E-mail : [acs.kh@al-hoty.com](mailto:acs.kh@al-hoty.com)  
Website: [www.alhotycalibration.com](http://www.alhotycalibration.com)



# Certificate of Calibration

Certificate No: 12406008

**Customer Name:** Al Hisan Factory  
**Address:** Dammam, Kingdom of Saudi Arabia

### Product Identification and Specification

Item Submitted: Water Meter  
Manufacturer: EMKO  
Model: EZM-9930  
Serial Number: 22092702-W  
Asset Number: N/A  
Customer P.O: N/A

Page No: 1 of 2  
Received Date: 01 June 2024  
Calibration Date: 01 June 2024  
Calibration Due Date: 01 June 2025  
Certificate Issue Date: 06 June 2024  
Received Condition: In tolerance  
Returned Condition: In tolerance

**Calibration Procedure:** ICP-I-078

**Summary of Procedure:** The Unit Under Test (UUT), a water meter was calibrated by measuring the actual output water using a volumetric graduated container.

**Environmental Condition:** 43.3 ±1.1°C / 21.8 ±0.7%RH

**Calibration Results:** (see the next page)

### Calibration Notes:

*Basis of Tolerance: ASTM C94/C94M-23  
Max. Capacity: 999 Liters / Min. Division: 1L x10 Liters  
Location: Plant # 1, Abu Hadriya, Dammam  
The statement of compliance was based on the performance of the unit under test (UUT) against ASTM C94/C94M-23 requirements and taking the measurement uncertainty into account applies decision rule by metrological analysis.*

### Standard Used to Calibrate Instrument:

Description	ACS Number	Cal Due Date	Traceability
Volumetric Graduated Container	ACS-KH-FV008A	23 July 2024	1S240117 (METAS/NMCC, KSA/NIST, USA)
Digital Temperature Humidity Meter	ACS-KH-TE025	15 April 2025	1S240415 (NIST, USA / NMCC, KSA)

Calibrated By: \_\_\_\_\_  
Calibration Tech. (Stamp)



Approved By: \_\_\_\_\_  
Manager

The reported expanded uncertainty of measurement is stated as the standard uncertainty measurement multiplied by the coverage factor k=2, providing a level of confidence of approximately 95%.

This certifies that the above listed instrument has been calibrated using standards whose accuracies are traceable to national or international standards and in accordance with the quality system conform to ISO/IEC 17025:2017.

This certificate applies only to the item described on the certificate.

## AL-HOTY CALIBRATION SERVICES

Water Meter	Certificate Number	12406008
Serial Number: 22092702	Page:	2 of 2

### Calibration Results


Test	UUT Setting	Measured Output	Error	Tolerance	Uncertainty	Compliance
Description		(liters)	(liters)	(liters)	(liters)	
Meter Accuracy	200	200	0	± 3	± 5.8	P
Test						

#### Notation:

- P - Pass
- \* P - Conditional Pass
- \* F - Conditional Fail
- F - Fail

End of Certificate





**AL-HOTY CALIBRATION SERVICES**  
A BRANCH OF AL-HOTY CO. LTD.

Calibration Laboratory  
C.R.2051015391  
25<sup>th</sup> Corner Zulfı St, Thuqbah,  
Al-Khobar 31952 - Kingdom of Saudi Arabia  
Tel. : (013) 864 4150 / 894 8020 / 894 5452  
Fax : (013) 898 1644 / 894 3980  
E-mail : [acs.kh@al-hoty.com](mailto:acs.kh@al-hoty.com)  
Website: [www.alhotycalibration.com](http://www.alhotycalibration.com)



### Certificate of Calibration

Certificate No: 12406352

**Customer Name:** Al Hussan Contracting  
**Address:** Dammam, Kingdom of Saudi Arabia

**Product Identification and Specification**

Item Submitted: Compression Machine	Page No: 1 of 2
Manufacturer: NL Scientific	Received Date: 27 June 2024
Model: NL 4000X/032G	Calibration Date: 27 June 2024
Serial Number: 0423120506	Calibration Due Date: 27 June 2025
Asset Number: N/A	Certificate Issue Date: 30 June 2024
Customer P.O: N/A	Received Condition: Refer to cal. results
	Returned Condition: Refer to cal. results

**Calibration Procedure:** ICP-I-063

**Summary of Procedure:** The Unit Under Test (UUT), a compression machine has been calibrated and verified to the requirements of BS EN ISO 7500-1: 2018 against a reference standard load cell and digital indicator.

**Environmental Condition:** 31.0 ± 1.4°C / 39 ± 5%RH

**Calibration Results:** (see the next page)

**Calibration Notes:**

*Basis of Requirements : BS EN ISO 7500-1: 2018*

*Location: Dammam*

*The Statement of Compliance is based on the performance of the Unit Under Test (UUT) against BS EN ISO 7500-1: 2018 requirements and taking the measurement uncertainty into account applies decision rule by metrological analysis.*

*The equipment shall be reverified if it is moved to a new location necessitating dismantling or if it is subject to major repairs or adjustments.*

**Standard Used to Calibrate Instrument:**

Description	ACS Number	Cal Due Date	Traceability
3000 kN Load Cell w/ Digital Indicator	ACS-KH-FT016/FT012	17 January 2025	C140-08-1-07A1723 (NIST, USA)
Digital Thermo-Hygrometer	ACS-KH-TH033	30 September 2024	1S230931 (NMCC, KSA / NIST, USA)

Calibrated By: \_\_\_\_\_  
Calibration Tech. (Stamp)



Approved By: \_\_\_\_\_  
Manager

The reported expanded uncertainty of measurement is stated as the standard uncertainty measurement multiplied by the coverage factor k=2, providing a level of confidence of approximately 95%.  
This certifies that the above listed instrument has been calibrated using standards whose accuracies are traceable to national or international standards and in accordance with the quality system conform to ISO/IEC 17025:2017

## AL-HOTY CALIBRATION SERVICES

Compression Machine Serial Number: 0423120506	Certificate Number: 12406352 Page: 2 of 2
--	--

### Calibration Results

Type	Digital Indicator	Range	2000 kN
Serial Number	0423120506	Scale Division/Increment	0.01 / 0.1 kN

Mode of Test	Increasing Force in Compression	Method of Test	True Force
--------------	---------------------------------	----------------	------------

### Relative Accuracy, Repeatability, Zero and Resolution

Constant Force (kN)	UUT Reading (kN)				Mean (kN)	Accuracy (%)	Relative Repeatability Error (%)	Measurement Uncertainty (kN)	Compliance
	Test 1	Test 2	Test 3	Test 4 <small>Note (1)</small>					
300	303.72	302.93	300.83	N/A	302.49	+0.83	0.96	±2.3	*P
600	603.59	602.04	600.24		601.96	+0.33	0.56	±2.6	P
900	902.91	900.98	898.72		900.87	+0.10	0.47	±3.3	P
1200	1201.8	1200.4	1198.4		1200.2	+0.02	0.28	±2.7	P
1500	1500.0	1498.5	1495.6		1498.0	-0.13	0.29	±3.5	P

Relative Zero Error				Relative Resolution		
Test 1 (%)	Test 2 (%)	Test 3 (%)	Mean (%)	Resolution / Readability (%)		
0.00	0.00	0.00	0.00	0.01 / 0.1 kN		0.003 / 0.008

Note (1) Test 4 is use during the verification of accessory devices (pointer, recorder) and its not included in the computation of mean.

The testing machine is normally used  with  without accessories.

Type of accessories : None

#### Classification

Accuracy	Class 1	Compression from <u>300 kN</u> up to <u>1500 kN</u>
Repeatability	Class 1	Compression from <u>300 kN</u> up to <u>1500 kN</u>
Zero	Class -	-
Resolution	Class 1	Compression from <u>300 kN</u> up to <u>1500 kN</u>

#### Notation:

P - Pass  
 \* P - Conditional Pass  
 \* F - Conditional Fail  
 F - Fail

End of Certificate







**ZAIN Eastern Est.**

Development Technics



مؤسسة زين الشرقية

للتقنيات المتطورة

S.NO.4405


<b>CLIENT</b>	<b>BARIQA WATER FACTORY</b>
<b>DATE OF SAMPLE</b>	22 June 2024
<b>DATE OF ANALYSIS</b>	25 June 2024
<b>TYPE OF ANALYSIS</b>	Sweet Water

TEST	CONTROL LIMITS	RESULTS
	HIGHEST DESIRABLE	
APPEARANCE	—	CLEAR
TASTE	—	UNOBJECTIONABLE
ODOR	—	UNOBJECTIONABLE
TEMPRATURE	—	25.5 O C
PH VALUE	6.5-8.5	6.80
CONDUCTIVITY	—	215 us / cm
T.D.S	500	145 mg / l
M-ALAKALINITY	200	12 mg / l as CaCO <sub>3</sub>
BICARBONATE	75	13 mg / l as HCO <sub>3</sub>
CHLORIDE	200	35 mg / l as Cl <sup>-</sup>
TOTAL HARDNESS	100	20 mg / l as CaCO <sub>3</sub>
CALCIUM HARDNESS	75	12 mg / l as CaCO <sub>3</sub>
MAGNESIUM HARDNESS	30	07 mg / l as CaCO <sub>3</sub>
POTASSIUM	4.0	2 mg / l as K <sup>+</sup>
SULPHATE	200	8 mg / l as SO <sub>4</sub> <sup>2-</sup>
TOTAL CHLORINE	0.2-0.7	0.6 mg / l as Cl <sub>2</sub>
SILICA	—	20 mg / l as SiO <sub>2</sub>
IRON(TOTAL)	0.1	0.01 mg / l as Fe <sup>+</sup>
ZINC	—	0.02 mg / l
MICROBIOLOGY SRB	—	0.00 mg / l

MOHAMED HASSAN .

CHEMIST  
WPSA-LAB





DATE : 22.04.2024

CERTIFICATE NO. 244447A

Issued to: Al Diyar Al Mumaazah

TEST CERTIFICATE

ACCORDING TO ASTM C150/C150 M  
ORDINARY PORTLAND CEMENT (TYPE-I)

CHEMICAL ANALYSIS			
PARAMETERS		RESULT OBTAINED %	STANDARD REQUIREMENT
SILICON DIOXIDE	SiO2	21.08	LIMIT NOT SPECIFIED
ALUMINIUM OXIDE	Al2O3	4.72	LIMIT NOT SPECIFIED
FERRIC OXIDE	Fe2O3	3.39	LIMIT NOT SPECIFIED
CALCIUM OXIDE	CaO	64.08	LIMIT NOT SPECIFIED
MAGNESIUM OXIDE	MgO	1.23	MAX. 6.0 %
SULFUR TRI OXIDE	SO3	2.92	MAX. 3.0 %
LOSS ON IGNITION	LOI	2.12	MAX. 3.0 %
INSOLUBLE RESIDUE	IR	1.18	MAX. 1.5 %
EQUIVALENT ALKALIES	Na2O + 0.658 K2O	0.55	OPTIONAL AS PER ASTM C33
TRICALCIUM SILICATE	C3S	55.78	LIMIT NOT SPECIFIED
TRICALCIUM ALUMINATE	C3A	6.77	LIMIT NOT SPECIFIED
TETRACALCIUM ALUMINOFERRITE	C4AF	10.31	LIMIT NOT SPECIFIED
CHLORIDE	Cl <sup>-</sup>	0.02	LIMIT NOT SPECIFIED
PHYSICAL TESTS			
SETTING TIME (VICAT)- MINUTES	INITIAL	110	NOT LESS THAN 45 MINUTES
	FINAL	165	NOT MORE THAN 375 MINUTES
FINENESS (BLAINE) SPECIFIC SURFACE	m2/kg	329	MIN. 260 M2/KG
AUTOCLAVE EXPANSION	%	0.04	LIMIT NOT SPECIFIED
AIRCONTENT MORTAR (% BY VOL)	%	8.3	MAX. 12 %
COMPRESSIVE STRENGTH - Mpa (psi)	3 DAYS	23.9 (3467)	MIN. 12.0 Mpa (1740 psi)
	7 DAYS	28.3 (4105)	MIN. 19.0 Mpa (2760 psi)
	28 DAYS	Result awaited	OPTIONAL PHYSICAL REQUIREMENT

We certify that the above test results are for the cement which complies with ASTM C 150/ C 150M for type -1 Cement representing dispatch

FROM: 07.04.24 TO: 13.04.24

for P & QC MANAGER



PLANT MANAGER  
FM-QC-08, Rev02

EASTERN PROVINCE CEMENT CO.

P.O. Box 4935 Dammam 31412 - Saudi Arabia  
Tel.: (0096613) 8312227 - Fax : (0096613) 8312000  
C.R. 2050813400 - Chamber of Commerce Membership (131)



شركة أسمنت المنطقة الشرقية

ج.م.س.ع. ٤٩٣٥ الدمام ٣١٤١٢ - المملكة العربية السعودية  
ت. ٨٣١٢٢٢٧ (٠١٣١٣٣) - ف. ٨٣١٢٠٠٠ (٠١٣١٣٣)  
س. ٢٠٥٠٨١٣٤٠٠ - ر.م.س.ع. ١٣٤٠٠ التجارية (١٣١)



DATE : 22.04.2024  
 CERTIFICATE NO. **244448/A**  
 Issued to: **Al Diyar Al Mumalazah**

**TEST CERTIFICATE**  
 ACCORDING TO ASTM C 150/ C150M  
 SULPHATE RESISTING PORTLAND CEMENT (TYPE- V)

CHEMICAL ANALYSIS			
		RESULT OBTAINED %	STANDARD REQUIREMENT
SILICON DIOXIDE	SiO2	21.62	LIMIT NOT SPECIFIED
ALUMINIUM OXIDE	Al2O3	3.83	LIMIT NOT SPECIFIED
FERRIC OXIDE	Fe2O3	5.27	LIMIT NOT SPECIFIED
CALCIUM OXIDE	CaO	63.94	LIMIT NOT SPECIFIED
MAGNESIUM OXIDE	MgO	1.51	MAX. 6.0 %
SULFUR TRI OXIDE	SO3	2.06	MAX. 2.3 %
LOSS ON IGNITION	LOI	1.47	MAX 3.0 %
INSOLUBLE RESIDUE	IR	0.73	MAX 1.5 %
EQUIVALENT ALKALIES	Na2O + 0.658 K2O	0.54	OPTIONAL AS PER ASTM C33
TRICALCIUM SILICATE	C3S	56.85	LIMIT NOT SPECIFIED
TRICALCIUM ALUMINATE	C3A	1.23	MAX. 5.0 %
TETRACALCIUM ALUMINOFERRITE	C4AF	16.02	LIMIT NOT SPECIFIED
TETRACALCIUM ALUMINOFERRITE+ TRICALCIUM ALUMINATE	C4AF+2C3A	18.49	MAX. 25 %
CHLORIDE	Cl <sup>-</sup>	0.02	LIMIT NOT SPECIFIED
PHYSICAL TESTS			
SETTING TIME ( VICAT)- MINUTES	INITIAL	110	NOT LESS THAN 45 MINUTES
	FINAL	160	NOT MORE THAN 375 MINUTES
FINENESS (BLAINE) SPECIFIC SURFACE	m2/kg	324	MIN. 260 M2/KG
AUTOCLAVE EXPANSION	%	0.03	LIMIT NOT SPECIFIED
AIRCCONTENT MORTAR (% BY VOL)	%	8.5	MAX. 12 %
COMPRESSIVE STRENGTH - Mpa (psi)	3 DAYS	17.8 (2582)	MIN. 8.0 Mpa (1160 psi)
	7 DAYS	22.0 (3191)	MIN. 15.0 Mpa (2180 psi)
	28 DAYS	Result awaited	MIN. 21.0 Mpa (3050 psi)

We certify that the above test results are for the cement which complies with ASTM C 150/ C 150M for type -V Cement representing dispatch

FROM: 07.04.24 TO: 13.04.24

*[Signature]*  
 P& QC MANAGER



*[Signature]*  
 PLANT MANAGER

FM-QC-09,Rev 02

**EASTERN PROVINCE CEMENT CO.**


P.O. Box 4395 Dammam 31412 - Saudi Arabia  
 Tel: (0096613) 8812222 - Fax: (0096613) 8812000  
 G.R. 2070013500 - Chamber of Commerce Membership (111)



www.epcco.com.sa

**شركة أسمنت المنطقة الشرقية**

ج.ب. 4395 الدمام 31412 - المملكة العربية السعودية  
 ت : (0096613) 8812222 - ف : (0096613) 8812000  
 رقم التسجيل 2070013500 - عضوية غرفة التجارة (111)




## LIST OF SOME CLIENTS

#	Project Name	Location	Quantity
1	Mufreh Marzoug Al Harbi Company	Dammam	bricks 400,000
2	Bayan Saleh Al Shawish Foundation	Dammam	bricks 100,000
3	King Fahd University	Dammam	bricks 100,000
4	A company of Miles	Dammam	bricks 500,000
5	Mayada Foundation	Dammam	bricks 40,000
6	Al-Drees Station	Dammam	bricks 60,000
7	Ministry of Defense Security Precautions	Dammam	bricks 50,000
8			
9			
10			
11			
12			



QUALITY

# Quality Control Manual



The following quality control guidelines are dictated by the management anxiety and concern that all elements produced at our factory shall comply with the required specification, standards and code of practice.

In this context, the following information are explicitly expounding the criteria for acceptance of the raw materials, of finished products and of manufacturing procedure. Unless specified by the client or his consultants, American standards shall prevail.

In order not to have any conflict of priorities, the quality assurance department is directly reporting to the highest management independently of production personnel. Quality of the production is strictly controlled at the two stages :-

Raw materials – by material testing laboratory.

Fabrication and finish products – by the QA/QC Engineer / Inspectors.

## STANDARD TESTING PROCEDURES

### 1. TEST ON BASIC & RAW MATERIALS

Special attention is given to the selection of the basic materials. Test are conducted regularly thus ensuring compliance with the relevant standards (ASTM, DIN, BS or any particular requirement of the client). When necessary, tests are conducted by an Independent

Testing Laboratory, on the special request by the client. Each delivery of basic material is checked visually. All materials are stored to avoid contamination and maintain cleanliness.





## 1.1. CEMENT

Cement is received with test certificates and delivery order. This certificate is sent to the Quality Control Engineer for scrutinizing. This may normally be reviewed after the material is used. If any problem is noticed, the Production Manager will be informed who will arrange to locate concrete elements produced with this cement.

Cement will be visually inspected for color and quantity. In the event of nonconformance, the foreman contacts the Production Manager for further action. After inspection, the Mixer Foreman signs the delivery note. The original DV is sent to the store keeper.

Once in six months, the cement will be tested in an independent laboratory for physical and chemical analysis. Results will be scrutinized and filed by the Quality Control Engineer for at least 3 years.

## 1.2. AGGREGATE

Laboratory foremen will receive the material and sign the Delivery note after satisfying himself that the material is of the right size.

Laboratory tests will be done on aggregates as follows.

Grading Test : once a week on the aggregates available in the aggregate storage area.

Quality Control Manager will verify the test results thereafter, the values will be entered in computer.

Other tests like acid soluble Chlorides and sulfates, Specific gravity, flakiness and water absorption will be done once every month.


## 1.4. BEACH SAND & DUNE SAND

Laboratory foremen receives the material and signs the delivery note after satisfying himself that the material is of the right size and quantity to an extent possible as per DV.

Laboratory tests will be done on aggregates as follows:

Grading Test : once a week on the aggregate available in the aggregate storage area.

Quality Control Manager will verify the test results thereafter, the values will be entered in computer.



Quality Control Engineer will scrutinize test results and filed for at least 3 years and laboratory Foremen will file a copy of the same in the laboratory.

Mixer foremen shall insure that this information is passed to mixer plant operator. Mixer operator will use the sand in recommended proportions.

## **1.5 PLASTISIZERS & ADMIXTURES**

Mixer foreman receives the test Certificate and Delivery Voucher . Test certificate is sent to the Quality Control Engineer for Verification.

Incase test report from the supplier shows a nonconformance, Production Manager will be notified and the consignment will be kept aside until further investigation is done and decision is taken in this regard.

## **1.6. WATER**

Potable water supplied by private supplier will be used for concrete and will be checked for chemical analysis in an independent laboratory once in three months.

## **1.7. MICRO SILICA**

Densified or intensified micro-silica are used for the production of concrete.

Production Manager is responsible for conducting the receiving inspection for micro-silica. Quantity and grade of the material mentioned on the bag will be inspected. Associated test certificates will be forwarded to the Quality Control Engineer for verification and filing.

## **1.8. REINFORCEMENT, EMBEDS & INSERTS etc.**

Detailed inspection of incoming materials to be carried out against specifications. Tensile strength (by independent laboratory), if required.





## 2. TEST ON CONCRETE

### 2.1. TEST ON FRESH CONCRETE

- Slump test (Delivery/ Mix).
- Density test (Daily/ Mix)
- Fresh concrete temperature (Daily/ Mix)

### 2.2. TEST ON HARDENED CONCRETE

#### 2.2.1. Compressive Strength

Samples of concrete are taken on a daily basis from each type of mix manufactured. Cylinder or cubes are cast and tested for compressive strength at the demoulding time and 3, 7, & 28 days. All results are recorded and graphical & statistical analysis made on a continuous basis .

The Production Manager will verify the cube test results on a daily basis. If the results are not as per requirement, then the precast components made with that concrete will be dealt as non conforming product. Engineering Manager or Structural Engineer will be informed and they will propose the corrective action or rejection of the element.

### 2.3. BATCHING PLANT CHECKING

In addition to the close control on the consistency of the concrete mixtures, the batch plant is visually inspected daily and scales calibration is performed by our staff on a monthly basis and by an independent firm on a bi-annum basis.

# PRECON TEST REPORTS





شركة معيار العربية للفحص  
Standard Arabia Inspection Co Ltd.

TESTING AND CALIBRATION DIVISION

# 6668, First Support Industrial Area, Al Jubail 3048-35717, KSA

C. R. No. 2055024044, C.O.C No. 174341

W: www.standardarabia.com | M: +966-50 762 6660 | T: +966- 13 367 0802

TEST REPORT

SAMPLING AND TESTING CONCRETE MASONRY UNITS AND RELATED UNITS  
ASTM C 140 – 13

CLIENT INFORMATION

Client : Precon Concrete & Block  
Address : Dammam, KSA  
Consultant : -  
Project Name : Concrete Batch Plant  
Project Location : Dammam, KSA

SAMPLE DETAILS

Sample Supplier : Precon  
Sample Description : 200x200x370-400 (Hollow)  
Sampling Date : 14 September 2024  
Lab. Reference : M-CON-11622  
Sampled by : Dixter

REPORT DETAILS

Report No. : TR-11622  
Date Reported : 18 September 2024  
Sales Order No. : 130  
CRN : 175  
Lab Location : Jubail

TEST/METHODS DETAILS

Date Tested : 17 September 2024  
Sampling Method : ASTM C 140 – 13  
Test Method : ASTM C 140 – 13  
Tested by : Dixter

S/N	Lab Ref. No.	DATE TESTED	LOAD kN	GROSS AREA mm <sup>2</sup>	GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	NET AREA mm <sup>2</sup>	NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)
A	M-CON-11622	17/09/24	385.1	76,950	5.00	4.94	48,352	7.96	7.87
B	M-CON-11622	17/09/24	375.4	76,950	4.88		48,352	7.76	
C	M-CON-11622	17/09/24	381.3	76,950	4.96		48,352	7.89	




REVIEWED BY (Lab Supervisor) Abhimanyu	APPROVED BY (Quality Manager) Fayaz M. Yousuff
---	---

Form No: MGT-TR-Con-09  
Issue No: 2 Date : May, 2017  
Rev No : 0

AL MONGITH AL AWAL LABORATORY FOR CONSTRUCTION  
Ibn Sina 2914, Al-Khobar 34627, K.S.A M: 050 6647770 E: info@mgthworld.com  
Page 1 of 1

This Document may be reproduced other than in full, except with the prior written approval of the issuing laboratory.  
These results pertain only to the item(s) tested as sampled by the client unless otherwise indicated.





شركة معيار العربية للفحص  
Standard Arabia Inspection Co Ltd.  
TESTING AND CALIBRATION DIVISION  
# 6668, First Support Industrial Area, Al Jubail 3048-35717, KSA  
C. R. No. 2055024044, C.O.C No. 174341  
W: www.standardarabia.com | M: +966 -50 762 6660 | E: +966- 13 367 0802

### TEST REPORT

#### SAMPLING AND TESTING CONCRETE MASONRY UNITS AND RELATED UNITS ASTM C 140 – 13


**CLIENT INFORMATION**  
Client : Precon Concrete & Block  
Address : Dammam, KSA  
Consultant : -  
Project Name : Concrete Batch Plant  
Project Location : Dammam, KSA

**REPORT DETAILS**  
Report No. : TR-11624  
Date Reported : 18 September 2024  
Sales Order No. : 130  
CRN : 175  
Lab Location : Jubail

**SAMPLE DETAILS**  
Sample Supplier : Precon  
Sample Description : 200 x 200 x 400 (Hollow)  
Sampling Date : 14 September 2024  
Lab. Reference : M-CON-11624  
Sampled by : Dixter

**TEST/METHODS DETAILS**  
Date Tested : 17 September 2024  
Sampling Method : ASTM C 140 – 13  
Test Method : ASTM C 140 – 13  
Tested by : Dixter

S/N	Lab Ref. No.	DATE TESTED	LOAD kN	GROSS AREA mm <sup>2</sup>	GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	NET AREA mm <sup>2</sup>	NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)
A	M-CON-11624	17/09/24	459.6	79,950	5.75	5.74	68,891	6.67	6.66
B	M-CON-11624	17/09/24	458.4	79,950	5.73		68,891	6.65	
C	M-CON-11624	17/09/24	458.9	79,950	5.74		68,891	6.66	



<b>REVIEWED BY (Lab Supervisor)</b> Abhimanyu	<b>APPROVED BY (Quality Manager)</b> Fayaz M. Yousuff
--	--

Form No: MGT-TR-Con-09  
Issue No: 2 Date : May, 2017  
Rev No : 0

AL MONGITH AL AWAL LABORATORY FOR CONSTRUCTION  
Ibn Sina 2914, Al-Khoher 34627, K.S.A. M: 050 6647770 E: info@mgworld.com  
Page 1 of 1

This Document may be reproduced other than in full, except with the prior written approval of the issuing laboratory.  
These results pertain only to the item(s) tested as sampled by the client unless otherwise indicated.






TEST REPORT

SAMPLING AND TESTING CONCRETE MASONRY UNITS AND RELATED UNITS  
ASTM C 140 – 13

<b>CLIENT INFORMATION</b>		<b>REPORT DETAILS</b>	
Client	: Precon Concrete & Block	Report No.	: TR-11620
Address	: Dammam, KSA	Date Reported	: 18 September 2024
Consultant	: -	Sales Order No.	: 130
Project Name	: Concrete Batch Plant	CRN	: 175
Project Location	: Dammam, KSA	Lab Location	: Jubail
<b>SAMPLE DETAILS</b>		<b>TEST/METHODS DETAILS</b>	
Sample Supplier	: Precon	Date Tested	: 17 September 2024
Sample Description	: 150x200x400 (Hollow)	Sampling Method	: ASTM C 140 – 13
Sampling Date	: 14 September 2024	Test Method	: ASTM C 140 – 13
Lab. Reference	: M-CON-11620	Tested by	: Dixter
Sampled by	: Dixter		

S/N	Lab Ref. No.	DATE TESTED	LOAD kN	GROSS AREA mm <sup>2</sup>	GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	NET AREA mm <sup>2</sup>	NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)
A	M-CON-11620	17/09/24	350.7	59,890	5.85	5.87	38,779	9.04	9.06
B	M-CON-11620	17/09/24	352.2	59,890	5.88		38,779	9.08	



<b>REVIEWED BY (Lab Supervisor)</b> Abhimanyu	<b>APPROVED BY (Quality Manager)</b> Fayaz M.Yousuff
--	---

Form No: MGT-TR-Con-09  
Issue No: 2 Date : May, 2017  
Rev No : 0

AL MONGITH AL AWAL LABORATORY FOR CONSTRUCTION  
Ibn Sina 2914, Al-Khobar 34627, K.S.A M: 050 6647770 E: info@mgworld.com  
Page 1 of 1

This Document may be reproduced other than in full, except with the prior written approval of the issuing laboratory.  
These results pertain only to the item(s) tested as sampled by the client unless otherwise indicated.






TEST REPORT

SAMPLING AND TESTING CONCRETE MASONRY UNITS AND RELATED UNITS  
ASTM C 140 – 13

<b>CLIENT INFORMATION</b>	<b>REPORT DETAILS</b>
Client : Precon Concrete & Block	Report No. : TR-11625
Address : Dammam, KSA	Date Reported : 18 September 2024
Consultant : -	Sales Order No. : 130
Project Name : Concrete Batch Plant	CRN : 175
Project Location : Dammam, KSA	Lab Location : Jubail
<b>SAMPLE DETAILS</b>	<b>TEST/METHODS DETAILS</b>
Sample Supplier : Precon	Date Tested : 17 September 2024
Sample Description : 300 x 200 x 400 (Hollow)	Sampling Method : ASTM C 140 – 13
Sampling Date : 14 September 2024	Test Method : ASTM C 140 – 13
Lab. Reference : M-CON-11625	Tested by : Dixter
Sampled by : Dixter	

S/N	Lab Ref. No.	DATE TESTED	LOAD kN	GROSS AREA mm <sup>2</sup>	GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	NET AREA mm <sup>2</sup>	NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)
A	M-CON-11625	17/09/24	570.6	119,800	4.76	4.74	74,131	7.76	7.69
B	M-CON-11625	17/09/24	565.4	119,800	4.72		74,131	7.62	




<b>REVIEWED BY (Lab Supervisor)</b> Abhimanyu	<b>APPROVED BY (Quality Manager)</b> Fayaz M. Yousuff
--	--

Form No: MGT-TR-Con-09  
Issue No: 2 Date : May, 2017  
Rev No : 0

AL MONGITH AL AWAL LABORATORY FOR CONSTRUCTION  
Ibn Sina 2914, Al-Khobar 34627, K.S.A M: 050 6647770 E: info@mgworld.com  
Page 1 of 1

This Document may be reproduced other than in full, except with the prior written approval of the issuing laboratory.  
These results pertain only to the item(s) tested as sampled by the client unless otherwise indicated.






TEST REPORT

SAMPLING AND TESTING CONCRETE MASONARY UNITS AND RELATED UNITS  
ASTM C 140 – 13

<b>CLIENT INFORMATION</b>		<b>REPORT DETAILS</b>	
Client	: Precon Concrete & Block	Report No.	: TR-11621
Address	: Dammam, KSA	Date Reported	: 18 September 2024
Consultant	:	Sales Order No.	: 130
Project Name	: Concrete Batch Plant	CRN	: 175
Project Location	: Dammam, KSA	Lab Location	: Jubail
<b>SAMPLE DETAILS</b>		<b>TEST/METHODS DETAILS</b>	
Sample Supplier	: Precon	Date Tested	: 17 September 2024
Sample Description	: 100x200x400 (Hollow)	Sampling Method	: ASTM C 140 – 13
Sampling Date	: 14 September 2024	Test Method	: ASTM C 140 – 13
Lab. Reference	: M-CON-11621	Tested by	: Dixter
Sampled by	: Dixter		

S/N	Lab Ref. No.	DATE TESTED	LOAD kN	GROSS AREA mm <sup>2</sup>	GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	NET AREA mm <sup>2</sup>	NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)
A	M-CON-11621	17/09/24	320.7	39,400	8.13	8.16	29,179	10.99	11.16
B	M-CON-11621	17/09/24	325.6	39,400	8.26		29,179	11.59	
C	M-CON-11621	17/09/24	318.9	39,400	8.09		29,179	10.92	



REVIEWED BY (Lab Supervisor) Abhimayu	APPROVED BY ( Quality Manager ) Fayaz M. Yousuff
--	---

Form No: MGT-TR-Con-09  
Issue No: 2 Date : May, 2017  
Rev No : 0

AL MONGITH AL AWAL LABORATORY FOR CONSTRUCTION  
Ibn Sina 2914, Al-Khobar 34627, K.S.A M: 050 6647770 E: info@mgworld.com  
Page 1 of 1

This Document may be reproduced other than in full, except with the prior written approval of the issuing laboratory.  
These results pertain only to the item(s) tested as sampled by the client unless otherwise indicated.





TEST REPORT

SAMPLING AND TESTING CONCRETE MASONRY UNITS AND RELATED UNITS  
ASTM C 140 – 13

CLIENT INFORMATION

Client : Precon Concrete & Block  
Address : Dammam, KSA  
Consultant :  
Project Name : Concrete Batch Plant  
Project Location : Dammam, KSA

REPORT DETAILS

Report No. : TR-11623  
Date Reported : 18 September 2024  
Sales Order No. : 130  
CRN : 175  
Lab Location : Jubail


SAMPLE DETAILS

Sample Supplier : Precon  
Sample Description : 200 x200 x400(Hollow Insulation)  
Sampling Date : 14 September 2024  
Lab. Reference : M-CON-11623  
Sampled by : Dlxter

TEST/METHODS DETAILS

Date Tested : 17 September 2024  
Sampling Method : ASTM C 140 – 13  
Test Method : ASTM C 140 – 13  
Tested by : Dlxter

S/N	Lab Ref. No.	DATE TESTED	LOAD kN	GROSS AREA mm <sup>2</sup>	GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	NET AREA mm <sup>2</sup>	NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)
A	M-CON-11623	17/09/24	585.6	79,910	7.33	7.35	71,510	8.19	8.22
B	M-CON-11623	17/09/24	595.4	79,910	7.45		71,510	8.33	
C	M-CON-11623	17/09/24	581.9	79,910	7.28		71,510	8.14	



REVIEWED BY (Lab Supervisor)	APPROVED BY
Isagani Hernandez	Tariq Al Rabiah (Chief Technical Officer)
Suresh Kumar	Rey Torrigue (Operations Manager)

Form No: MGT-TR-Con-09  
Issue No: 2 Date : May, 2017  
Rev No : 0

AL MONGITH AL AWAL LABORATORY FOR CONSTRUCTION  
Ibn Sina 2914, Al-Khobar 34627, K.S.A M: 050 6647770 E: info@mgworld.com  
Page 1 of 1

This Document may be reproduced other than in full, except with the prior written approval of the issuing laboratory.  
These results pertain only to the item(s) tested as sampled by the client unless otherwise indicated.







**TEST REPORT**

**SAMPLING AND TESTING CONCRETE MASONRY UNITS AND RELATED UNITS**  
**ASTM C 140 – 13**

**CLIENT INFORMATION**

Client : Precon Concrete & Block  
Address : Dammam, KSA  
Consultant : -  
Project Name : Concrete Batch Plant  
Project Location : Dammam, KSA

**REPORT DETAILS**

Report No. : TR-11626  
Date Reported : 18 September 2024  
Sales Order No. : 130  
CRN : 175  
Lab Location : Jubail


**SAMPLE DETAILS**

Sample Supplier : Precon  
Sample Description : 300 x200 x 400 (Hollow Insulation)  
Sampling Date : 14 September 2024  
Lab. Reference : M-CON-11626  
Sampled by : Dixter

**TEST/METHODS DETAILS**

Date Tested : 17 September 2024  
Sampling Method : ASTM C 140 – 12a  
Test Method : ASTM C 140 – 12a  
Tested by : Dixter

S/N	Lab Ref. No.	DATE TESTED	LOAD kN	GROSS AREA mm <sup>2</sup>	GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE GROSS COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	NET AREA mm <sup>2</sup>	NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)	AVERAGE NET COMPRESSIVE STRENGTH N/mm <sup>2</sup> (MPA)
A	M-CON-	17/09/24	470.6	79,860	5.89	5.96	71,600	6.57	6.65
B	M-CON-	17/09/24	467.2	79,860	5.85		71,600	6.52	
C	M-CON-	17/09/24	478.5	79,860	5.99		71,600	6.68	
D	M-CON-	17/09/24	488.4	79,860	6.12		71,600	6.82	



<b>REVIEWED BY (Lab Supervisor)</b> Abhimanyu	<b>APPROVED BY ( Quality Manager )</b> Fayaz M.Yousuff
--	---

Form No: MGT-TR-Con-09  
Issue No: 2 Date : May, 2017  
Rev No : 0


AL MONGITH AL AWAL LABORATORY FOR CONSTRUCTION  
Ibn Sina 2914, Al-Khobar 34627, K.S.A M: 050 6647770 E: info@mgtworld.com  
Page 1 of 1

This Document may be reproduced other than in full, except with the prior written approval of the issuing laboratory.  
These results pertain only to the item(s) tested as sampled by the client unless otherwise indicated.



A collage of safety equipment. On the left, a tan work boot with laces. In the center, a grey safety boot with a metal toe cap. On the right, a yellow hard hat. At the bottom, a pair of clear safety glasses with yellow-tinted lenses. The background is a mix of these items, with a white surface at the bottom.

# Safety Program



## 1. PROTECTION OF WORKERS


Appropriate “protective” clothing is available and is to be used when necessary in particular :

- Safety helmets are to be worn at all times.
- Safety boot / shoes are to be worn at all time.
- Safety harnesses are to be used as directed.
- Personal engaged in special tasks, such as welding, are to use appropriate protective equipment.
- Edge protection is to be erected as necessary to ensure that workmen are not exposed to an unacceptable level of risk.
- All ladders and scaffold towers are to be inspected prior to use. No-damaged items are to be used. Mobile scaffold towers are only to be used on a firm level base in accordance with the manufactures instruction. Ladders are always to be secured near the top or “footed” by a man at the bottom.

### Exceptionally adverse weather conditions

The interpretation of what is exceptionally adverse weather and whether work should be suspended due to there being an unacceptable level of risk either to the workmen or of doing damage to equipment or the structure resets with the senior person on site. The following must be considered.

- The effect of high winds on the safe handling of elements.
- The effect of bad visibility (i.e. fog or sandstorm) on the ability of crane operators to see the load or the banks – man.
- The effect of rain on working surface, ladders, scaffolds and the like.
- The danger of a lightning strike. Normally work should be stopped above ground level when lightning is in the vicinity



## Protection of third parties.

- The area where pre-cast erection is in progress should be designated as a prohibited area to all persons other than those involved in the erection.
- Loads should not be hoisted over areas where other persons are working.
- On the occasions that it is necessary to unload elements from vehicles parked on the public road arrangement must to keep the public outside the potential danger area.
- Any visitors to the site are to be forced to take the same safety precautions as those persons working there.

## FIRE PROTECTION AND PREVENTION PROGRAM

### A. INTRODUCTION

1. an cause serious damage to plant and property and serious injury or loss of life to personnel. Good housekeeping plays an important role in Fire Prevention Program.

2. To help prevent the outbreak or continued combustion of fire, the following rules at the Work site will be observed:

- a) All Hot work shall be under strictly controlled conditions.
- b) Electrical outlets shall not be overloaded.
- c) All smoking operatives will smoke in designated areas only.
- d) Non-sparking tools and equipment will be used in areas of high risk.
- e) Good housekeeping practices will be followed.
- f) Flammable gas cylinders will be stored in an upright position and segregated cylinders. from oxygen.
- g) Flammable substances will be stored in a segregated area.
- h) Faulty oxygen or acetylene hoses and gauges will be discarded.
- i) hot work is completed or during any period of meal breaks, oxygen and acetylene will be turned off at the gauges.



- j) Clothes or rags will not be hung to dry in the vicinity of heaters.
- k) Oily rags will not be discarded in containers with other materials.
- l) After welding and burning operations, the surrounding areas will be inspected for smoldering materials.

## B. FIRE PROTECTION EQUIPMENT

- temporary buildings, yards, storage areas and the workplace will have strategically located fire extinguishers.
- Designated fire wardens will inspect the extinguishers monthly and record the findings.
- Empty or damaged extinguishers will be placed.
- The correct type of extinguishers will be placed to the adjacent materials or substances.
- Types of extinguishers are:
  - Water – used for solid organic materials, wood, paper, cloth, etc.
  - Dry Powder – used for solid materials or liquids, oils, electrical equipment.
  - Carbon Dioxide can be used on all kinds of fires.

NOTE: Do not use water spray on electrical equipment.

## C. FIRE PREVENTION RULES

1. Combustible materials will not be placed near sources of ignition.
2. All employees will have familiarization courses on the use of extinguishers, fire prevention and protection techniques.
3. Emergency telephone numbers will be conspicuously posted at worksite and all employees will be familiar with these numbers and Alarm procedure.
4. Sufficient extinguishers of correct type will be conspicuously posted at worksite and all employees will be available for use.



5. Emergency Exits will be sign posted and well visible without any obstructions.
6. All plants and equipment will carry fire extinguishers.
7. Extinguishers will be placed in close proximity to “Hot Work” operation.
8. Housekeeping will be undertaken on regular basis.

## D. EMERGENCY PROCEDURES IN CASE OF FIRE

1. If any operative discovers a fire, he should:

- Raise the alarm.
- Attempt to extinguish the fire using local extinguishers.
- Be sure that the Exit is at your rear and escape is always possible.
- If the fire escalates, vacate the area.
- Await Emergency Services and direct them to the location of the fire.
- Never attempt to be a “Hero”. This can possibly put other personnel at risk in attempting your rescue.

2. To help prevent the outbreak or continued combustion of fire, the following rules at the Work site will be observed:

- a) All Hot work shall be under strictly controlled conditions.
- b) Electrical outlets shall not be overloaded.
- c) All smoking operatives will smoke in designated areas only.
- d) Non-sparking tools and equipment will be used in areas of high risk.
- e) Good housekeeping practices will be followed.
- f) Flammable gas cylinders will be stored in an upright position and segregated cylinders. from oxygen.
- g) Flammable substances will be stored in a segregated area.
- h) Faulty oxygen or acetylene hoses and gauges will be discarded.
- i) hot work is completed or during any period of meal breaks, oxygen and acetylene will be turned off at the gauges.



2. Upon hearing the alarm or being informed by word of mouth, all personnel will:

- Shut down all equipment.
- Vacate their place of work.
- Proceed immediately to their Allocated Assembly Points .
- A roll call is affected and each person is accounted for .
- No person returns to work until “All clear” is given .

## **E. LEU PERSONNEL IN EMERGENCY FIRE RESPON**

1. Incident Liaison Officer – Project Manager. Incident Liaison
2. Assistant – Safety Officer. Liaison Officer Site /Gen. Office –
3. Construction Supervisor. Emergency Marshals – Construction
4. Supervisors.
5. Wardens Foreman.

## **F. DUTIES**

### **1. INCIDENT LIAISON OFFICER**

- Report to AL-HOSAN Control Center (Project Manager’s Office / Reception).
- Liaise with Client Emergency Controller.
- Amalgamate accountability of all personnel.

### **2. INCIDENT LIAISON ASSISTANCE**

- COLLECT DAILY TIME SHEET (ALL PERSONNEL).
- Report to AL-HOSAN Control Center.
- Standby for further duties.



### **3. SITE LIAISON OFFICER –SITE/GENERAL OFFICE**

- Report to Incident Control Center.
- Monitor Events – Liaise with AL-HOSAN Central Office as required.
- Ensure two-way radio is operational.

### **4. SWITCHBOARD OPERATOR**

- Standby switchboard for duties as required.

### **5. NURSE**

- Standby switchboard for duties as required.

### **6. EMERGENCY MARSHALS**

- Report to Assembly Point (after obtaining copies of daily time sheets)
- Register all attendees. Report AL-HOSAN Control Center when headcount is completed.
- Standby – Await further instructions.

NOTE: A two-way operational radio should be carried.


### **7. DESIGNATED WARDENS**

- Tour site-ensure that all operatives leave their place of work (after switching off all engines).  
Confirm that site is clear – report to Emergency Marshals.
- Standby for further instructions.
- Maintain orderly control of workforce at assembly point.

### **8. SUB-CONTRACTOR SUPERVISOR**

- Ensure all operatives leave site (after switching all engines).
- Report with them to assembly point.
- Standby for further instructions.





## **EMERGENCY LOCATIONS, TELEPHONE NUMBERS & RADIO CHANNELS:**

- AL-HOSAN Emergency Control: Main Site Office –Radio
- AL-HOSAN Main Office (Off Site) – 341 2561
- Assembly Points: To be determined dependent upon site layout and procedures. The Assembly Points will be indicated by signs and explained to the employees.


## **FIRST –AID AND MEDICAL SERVICES PLAN**

### **A. POLICY**

- 1.It is the Company Policy to provide first-aid facilities, medical, and emergency services for employees who incur occupational injuries or illnesses.
2. The first-aid facilities on this project will be provided in accordance with Saudi Labor and Workmen Law Chapter-7, (Protection of Social Services, Labor & Workmen Law-Articles 134, 135 & 136)

### **B. RESPONSIBILITIES**

- 1.The responsibility for evaluation the scope of first-aid medical services required to meet the safety and health needs of the project is shared by the company's Safety Department, Project Manager and the company's Chief of Client.
2. The determination of First Aid and Medical Services elements shall be completed no later than the pre-job conference .



1. The above listed items will be furnished in proportion to the number of workmen.
2. Signs will be posted in conspicuous places in the work sites to indicate the location of
3. The first-aid cabinet and the name of the workman in charge of first-aid facility.
4. The first-aid cabinet will be placed under the supervision of an attendant, who shall ensure that the cabinet is well stocked at all times.
5. The first-aid cabinet shall contain the first-aid supplies only.

## **G. FIRST – AID POSTING**

1. Contractor shall post notices indicating the following:
  - a. The name of the person who is in charge of the first-aid cabinet.
  - b. The hospital to which any injured person, that requires hospital treatment is to be sent.
  - c. The telephone number of the doctor or the first-aid attendant employed by the company.
  - d. The emergency telephone number to be called for assistance.


## **H. EMERGENCY TRANSPORTATION**

1. A jobsite dedicated emergency vehicle (ambulance) will be provided since in the near vicinity there is no immediate means of communication to take the injured or seriously ill person to the nearest designated hospital or clinic. The ambulance will be properly marked and adequately supplied.
2. The ambulance will be equipped, as a minimum, with the following supplies:  
A suitable type of stretcher Portable oxygen Splint for bone fractures  
Bandages/rubber tourniquet Sterile washbasin .
3. The Project Manager will appoint drivers for emergency duties and their names will appear on the designated competent person list.

## **I. FIRST-AID RECORDS**

A Site Register is maintained to keep the medical records of all injuries treated.

# Pictures Of Some Products














































## CONTACT DETAILES

Tel: 013 8377773 fax: 0138373218

E-mail: [precon.alhossan@gmail.com](mailto:precon.alhossan@gmail.com)

website Address: [www.precon.sa](http://www.precon.sa)

P.O.Box2447 Dammam 31451 - Kingdom of Saudi Arabia